



Santa Clara Valley Water District Recycled Water Committee Meeting

Headquarters Building Boardroom
5700 Almaden Expressway, San Jose, CA 95118

Join Zoom Teleconference:
<https://valleywater.zoom.us/j/99518153521>

REGULAR MEETING AGENDA

**Wednesday, May 22, 2024
12:00 PM**

District Mission: Provide Silicon Valley safe, clean water for a healthy life, environment and economy.

RECYCLED WATER COMMITTEE

Tony Estremera - District 6, Chair
Richard Santos - District 3, Vice Chair
Jim Beall - District 4, Member

During the COVID-19 restrictions, all public records relating to an open session item on this agenda, which are not exempt from disclosure pursuant to the California Public Records Act, that are distributed to a majority of the legislative body, will be available to the public through the legislative body agenda web page at the same time that the public records are distributed or made available to the legislative body. Santa Clara Valley Water District will make reasonable efforts to accommodate persons with disabilities wishing to participate in the legislative body's meeting. Please advise the Clerk of the Board Office of any special needs by calling (408) 265-2600.

KIRSTEN STRUVE
Committee Liaison
Nicole Merritt
Assistant Deputy Clerk II
Office/Clerk of the Board
(408) 630-32623262
nmerritt@valleywater.org

Note: The finalized Board Agenda, exception items and supplemental items will be posted prior to the meeting in accordance with the Brown Act.

Santa Clara Valley Water District
Recycled Water Committee
REGULAR MEETING AGENDA

Wednesday, May 22, 2024

12:00 PM

Headquarters Building Boardroom
5700 Almaden Expressway, San Jose, CA 95118

Join Zoom Meeting:
<https://valleywater.zoom.us/j/99518153521>

*****IMPORTANT NOTICES AND PARTICIPATION INSTRUCTIONS*****

Santa Clara Valley Water District (Valley Water) Board of Directors/Board Committee meetings are held as a “hybrid” meetings, conducted in-person as well as by telecommunication, and is compliant with the provisions of the Ralph M. Brown Act.

To maximize public safety while still maintaining transparency and public access, members of the public have an option to participate by teleconference/video conference or attend in-person. To observe and participate in the meeting by teleconference/video conference, please see the meeting link located at the top of the agenda. If attending in-person, you are required to comply with **Ordinance 22-03 - AN ORDINANCE OF THE SANTA CLARA VALLEY WATER DISTRICT SPECIFYING RULES OF DECORUM FOR PARTICIPATION IN BOARD AND COMMITTEE MEETINGS** located at <https://s3.us-west-2.amazonaws.com/valleywater.org.if-us-west-2/f2-live/s3fs-public/Ord.pdf>

In accordance with the requirements of Gov. Code Section 54954.3(a), members of the public wishing to address the Board/Committee during public comment or on any item listed on the agenda, may do so by filling out a Speaker Card and submitting it to the Clerk or using the “Raise Hand” tool located in the Zoom meeting application to identify yourself in order to speak, at the time the item is called. Speakers will be acknowledged by the Board Chair in the order requests are received and granted speaking access to address the Board.

- Members of the Public may test their connection to Zoom Meetings at: <https://zoom.us/test>
- Members of the Public are encouraged to review our overview on joining Valley Water Board Meetings at: <https://www.youtube.com/watch?v=ToJpYCxXm0>

Valley Water, in complying with the Americans with Disabilities Act (ADA), requests individuals who require special accommodations to access and/or participate in Valley Water Board of Directors/Board Committee meetings to please contact the Clerk of the Board’s office at (408) 630-2711, at least 3 business days before the scheduled meeting to ensure that Valley Water may assist you. This agenda has been prepared as required by the applicable laws of the State of California, including but not limited to, Government Code Sections 54950 et. seq. and has not been prepared with a view to informing an investment decision in any of Valley Water’s bonds, notes or other obligations. Any projections, plans or other forward-looking statements

included in the information in this agenda are subject to a variety of uncertainties that could cause any actual plans or results to differ materially from any such statement. The information herein is not intended to be used by investors or potential investors in considering the purchase or sale of Valley Water's bonds, notes or other obligations and investors and potential investors should rely only on information filed by Valley Water on the Municipal Securities Rulemaking Board's Electronic Municipal Market Access System for municipal securities disclosures and Valley Water's Investor Relations website, maintained on the World Wide Web at <https://emma.msrb.org/> and <https://www.valleywater.org/how-we-operate/financebudget/investor-relations>, respectively.

Under the Brown Act, members of the public are not required to provide identifying information in order to attend public meetings. Through the link below, the Zoom webinar program requests entry of a name and email address, and Valley Water is unable to modify this requirement. Members of the public not wishing to provide such identifying information are encouraged to enter "Anonymous" or some other reference under name and to enter a fictional email address (e.g., attendee@valleywater.org) in lieu of their actual address. Inputting such values will not impact your ability to access the meeting through Zoom.

Join Zoom Meeting:

<https://valleywater.zoom.us/j/99518153521>

Meeting ID: 995 1815 3521

Join by Phone:

1 (669) 900-9128, 99518153521#

1. CALL TO ORDER:

1.1. Roll Call.

2. TIME OPEN FOR PUBLIC COMMENT ON ANY ITEM NOT ON THE AGENDA.

Notice to the public: Members of the public who wish to address the Board/Committee on any item not listed on the agenda may do so by filling out a Speaker Card and submitting it to the Clerk or using the "Raise Hand" tool located in the Zoom meeting application to identify yourself to speak. Speakers will be acknowledged by the Board/Committee Chair in the order requests are received and granted speaking access to address the Board/Committee. Speakers' comments should be limited to three minutes or as set by the Chair. The law does not permit Board/Committee action on, or extended discussion of, any item not on the agenda except under special circumstances. If Board/Committee action is requested, the matter may be placed on a future agenda. All comments that require a response will be referred to staff for a reply in writing. The Board/Committee may take action on any item of business appearing on the posted agenda.

3. APPROVAL OF MINUTES:

3.1. Approval of March 27, 2024 Recycled Water Committee Minutes. [24-0490](#)

Recommendation: Approve the minutes.

Manager: Candice Kwok-Smith, 408-630-3193

Attachments: [Attachment 1: 032724 RWC Meeting Minutes](#)

Est. Staff Time: 5 Minutes

4. REGULAR AGENDA:

4.1. Receive Purified Water Program Update including Partnerships with the Cities of San Jose and Santa Clara and Provide Feedback. [24-0432](#)

Recommendation: Receive an update and provide feedback on the following topics:

- A. Collaboration effort with cities of San Jose and Santa Clara
- B. Development of a roadmap
- C. Update on consultant agreements; and
- D. Outreach

Manager: Kirsten Struve, 408-630-3138

Attachments: [Attachment 1: PowerPoint](#)

Est. Staff Time: 10 Minutes

4.2. Receive an Update on Valley Water's Efforts to Actively Engage in Direct Potable Reuse (DPR). [24-0434](#)

Recommendation: Receive an update on DPR regulations and DPR Workshop.

Manager: Kirsten Struve, 408-630-3138

Est. Staff Time: 5 Minutes

4.3. Receive South Santa Clara County Water Reuse Collaboration Update and Provide Feedback. [24-0431](#)

Recommendation: Receive an update and provide feedback on South Santa Clara County Water Reuse Collaboration.

Manager: Kirsten Struve, 408-630-3138

Attachments: [Attachment 1: PowerPoint](#)

[Attachment 2: Recycled Water Master Plan](#)

Est. Staff Time: 10 Minutes

4.4. Receive the Desalination Engineering Feasibility Study Update. [24-0149](#)
Recommendation: Receive update on the procurement process for a desalination engineering feasibility study and discuss next steps.
Manager: Kirsten Struve, 408-630-3138
Attachments: [Attachment 1: PowerPoint](#)
Est. Staff Time: 5 Minutes

4.5. Receive Update on Bottling Purified and Water Tasting Station at the Silicon Valley Advanced Water Purification Center. [24-0237](#)
Recommendation: Receive information on efforts to bottle advanced purified water for demonstration and outreach purposes.
Manager: Kirsten Struve, 408-630-3138
Attachments: [Attachment 1: PowerPoint](#)
Est. Staff Time: 10 Minutes

4.6. Receive an Update on Federal and State Grant Opportunities for Recycled Water Projects. [24-0433](#)
Recommendation: Receive an update on federal and state grant opportunities for recycled water projects.
Manager: Marta Lugo, 408-630-2237
Attachments: [Attachment 1: PowerPoint](#)
Est. Staff Time: 5 Minutes

4.7. Receive and Discuss the 2024 Recycled Water Committee (RWC) Work Plan, and Provide Feedback on Upcoming Discussion Items, and Upcoming Meeting Date. [24-0491](#)
Recommendation: Receive information on the 2024 RWC Work Plan, and provide feedback on upcoming discussion items and next meeting date.
Manager: Candice Kwok-Smith, 408-630-3193
Attachments: [Attachment 1: 2024 Revised RWC Work Plan](#)
Est. Staff Time: 5 Minutes

5. CLERK REVIEW AND CLARIFICATION OF COMMITTEE REQUESTS.

This is an opportunity for the Clerk to review and obtain clarification on any formally moved, seconded, and approved requests and recommendations made by the Committee during the meeting.

6. ADJOURN:

6.1. Adjourn to Regular Meeting at 12:00 p.m., on June 26, 2024.

THIS PAGE INTENTIONALLY LEFT BLANK



Santa Clara Valley Water District

File No.: 24-0490

Agenda Date: 5/22/2024

Item No.: 3.1.

COMMITTEE AGENDA MEMORANDUM Recycled Water Committee

Government Code § 84308 Applies: Yes No
(If "YES" Complete Attachment A - Gov. Code § 84308)

SUBJECT:

Approval of March 27, 2024 Recycled Water Committee Minutes.

RECOMMENDATION:

Approve the minutes.

SUMMARY:

In accordance with the Ralph M. Brown Act, a summary of Committee discussions, and details of all actions taken by the Committee, during all open and public Committee meetings, is transcribed and submitted to the Committee for review and approval.

Upon Committee approval, minutes transcripts are finalized and entered into Valley Water's historical records archives and serve as historical records of the Committee's meetings.

ENVIRONMENTAL JUSTICE AND EQUITY IMPACT:

The approval of minutes is not subject to environmental justice analysis.

ATTACHMENTS:

Attachment 1: 032724 RWC Meeting Minutes

UNCLASSIFIED MANAGER:

Candice Kwok-Smith, 408-630-3193

THIS PAGE INTENTIONALLY LEFT BLANK



RECYCLED WATER COMMITTEE MEETING

DRAFT MINUTES

**REGULAR MEETING
WEDNESDAY, MARCH 27, 2024
12:00 PM**

(Paragraph numbers coincide with agenda item numbers)

1. CALL TO ORDER:

A regular meeting of the Santa Clara Valley Water District (Valley Water) Recycled Water Committee (Committee) was called to order in the Valley Water Headquarters Building Boardroom at 5700 Almaden Expressway, San Jose, California, and by Zoom teleconference, at 12:00 p.m.

1.1. Roll Call.

Committee members in attendance were District 4 Director Jim Beall, District 3 Vice Chairperson Richard P. Santos, and District 6 Director Tony Estremera, Chairperson presiding, constituting a quorum of the Committee.

Staff members in attendance were: Brandon Adriano, Gina Adriano, Karen Adriano, Hossein Ashktorab, Aaron Baker, Nastaran Basiri, Kendra Boutros, Lakeisha Bryant, James Downing, Andrew Gschwind, Jiana Escobar, Rachael Gibson, Vincent Gin, Jason Gurdak, Zachary Helsley, Lei Hong, Girlie Jacobson, Candice Kwok-Smith, Emelia Lamas, Nicole Merritt, Mario Rivas, Don Rocha, Kirsten Struve, Charlene Sun, Darin Taylor, Pariya Torkaman, David Tucker, Kristen Yasukawa, and Beckie Zisser.

Public in attendance were: Molly Culton and Katja Irvin (Sierra Club), Jan Davel (CDM Smith), Pedro Hernandez (City of San Jose), and Eric Zagol (Mott MacDonald).

2. TIME OPEN FOR PUBLIC COMMENT ON ANY ITEM NOT ON THE AGENDA:

Chairperson Estremera declared time open for public comment on any item not on the agenda. There was no one who wished to speak.

2.1. Election of 2024 Recycled Water Committee (RWC) Chairperson and Vice Chairperson.

Recommendation: Nominate and elect the 2024 RWC Chairperson and Vice Chairperson.

Public Comments:
None.

It was moved by Vice Chairperson Santos and seconded by Director Beall and unanimously carried that Chairperson Estremera remain Chairperson and Vice Chairperson Santos remain Vice Chairperson.

3. APPROVAL OF MINUTES:

3.1. Approval of January 31, 2024 Recycled Water Committee Meeting Minutes.

Recommendation: Approve the minutes.

The Committee considered the attached minutes of the January 31, 2024 Committee meeting.

Public Comments:
None.

It was moved by Vice Chairperson Santos and seconded by Chairperson Estremera, and unanimously carried that the minutes be approved.

4. REGULAR AGENDA:

4.1. Receive Purified Water Program Update Including Partnerships with Cities of San Jose and Santa Clara and Provide Feedback.

Recommendation: Receive an update and provide feedback on the following topics:

- A. Collaboration effort with the Cities of San Jose and Santa Clara;
- B. Development of a roadmap to develop needed agreements, including mutual objectives, timelines, and resources needed to complete agreements within two years; and
- C. Outreach

Kirsten Struve reviewed the information on this item, per the attached Committee Agenda Memo.

Kirsten Struve and Hossein Ashktorab were available to answer questions.

Public Comments:
None.

The Committee received the information, took no formal action, and noted the following:

- The Committee confirmed that the staff outreach included updates to the interested parties of the Treatment Plant Advisory Committee (TPAC).
- The Committee confirmed that the demonstration facility will break ground in 3-5 years dependent upon the modification of existing agreements, staff anticipate looking to bid on a designer in the next fiscal year and are

Attachment 1

currently working on determining the facility's water flow up to 1 million gallons per day (MGD).

- The Committee noted that the nutrient regulations may affect recycled water projects, but that the City of San Jose has processes in place to meet the nutrient regulations and Valley Water is compensating for City staff assistance for the purified water project.
- Director Beall requested for staff outreach to schedule a pending tour request for the Silicon Valley Leadership Group to support with federal/state funding, requested for staff follow up on a concept plan snapshot, and noted interest in the upcoming Water 101 Academy for public engagement.

4.2. Receive Purified Water Program Update Including Partnerships with Cities of Palo Alto and Mountain View and Provide Feedback.

Recommendation:

- A. Receive an update on Purified Water Program including partnership with Cities of Palo Alto and Mountain View.
 - i. Collaboration Efforts with Cities
 - ii. Public Private Partnership
 - iii. Outreach
- B. Provide feedback on the planned activities to put the project on hold per the Board's February 27, 2024 decision, specifically.
 - i. Meet with P3 teams and cancel P3 procurement
 - ii. Put development of lease and O&M agreement on hold
 - iii. Notify regulators
 - iv. Focus resources on San Jose Purified Water Project
 - v. Update project website information
 - vi. Complete a change management memorandum (CMM) to place the project on the unfunded Capital Improvement Program (CIP) list and submit to the CIP Committee.

Kirsten Struve reviewed the information on this item, per the attached Committee Agenda Memo, and per the information contained in Attachment 1.

Kirsten Struve and Hossein Ashktorab were available to answer questions.

Public Comments:

None.

The Committee received the information, took no formal action, and noted the following:

- The Committee noted the Palo Alto Purified Water Project being put on the Capital Improvement Program (CIP) unfunded list due to project affordability.
- The Committee confirmed the potential pipeline is being evaluated as part of the San Jose direct potable reuse (DPR) project to determine the best opportunities for capacities in the system for a 24,000-acre foot per year

- facility for a new water supply with flexibility to be used for treatment plants or groundwater recharge.
- The Committee confirmed the Palo Alto project will likely be modeled as a direct potable reuse back up project on the Water Supply Master Plan.
- The Committee confirmed support of maintaining ongoing partnerships and good relationships with Palo Alto, Mountain View, and Sunnyvale and noted continuing funding of Palo Alto's salt removal facility per the 2019 joint agreement to expand their non-potable recycled water use. The Committee also supported staff's wrap up activities.

4.3. Consider the Draft Agenda for the April 18th, 2024 Joint Recycled Water Policy Advisory Committee with the Cities of San Jose and Santa Clara and Provide Feedback.

Recommendation:

- A. Consider the draft agenda for the April 18th, 2024, Joint Recycled Water Policy Advisory Committee for review, which includes coordination on the Silicon Valley Advanced Water Purification Center and building strong collaborative relationships with San Jose and Santa Clara; and
- B. Provide feedback and recommendations to staff as necessary

Hossein Ashktorab reviewed the information on this item, per the attached Committee Agenda Memo.

Hossein Ashktorab, Kirsten Struve, and Rachael Gibson were available to answer questions.

Public Comments:
None.

The Committee received the information, took no formal action, and noted the following:

- The Committee confirmed that amending agreements will be possible for fast tracking the process for the demonstration facility and then staff will work on new agreements and negotiations for the future larger project.
- The Committee confirmed support of resolving potential obstacles or disputes at future joint meetings to streamline project processes and noted staff's confirmation of no current potential issues.
- The Committee confirmed that staff is continuing to evaluate stormwater purification options via the RWC Work Plan and the Water Supply Master Plan and has lead development of stormwater resource plans in the North and South Counties to assist cities in receiving funding for their stormwater capture projects.
- The Committee noted the External Affairs staff's confirmation of follow up on providing talking points to the Committee regarding stormwater for public outreach.
- The Committee noted that stormwater purification is on the RWC Work Plan and stormwater capture is on the Water Conservation and Demand Management Committee's Work Plan which is now called the Water Supply and Demand Management Committee.

4.4. Receive Update on the Recycled Water Goal for the Water Supply Master Plan 2050; and Recommend to Valley Water's Board a Potable Reuse Goal.

Recommendation: A. Receive information and provide feedback on potential water reuse goal update; and
B. Recommend to Valley Water's Board a potable reuse goal of 24,000 Acre Feet per Year (AFY) by 2035 as well as a long term vision to maximize water reuse in the county for inclusion in the Water Supply Mast Plan 2050.

Zachary Helsley reviewed the information on this item, per the attached Committee Agenda Memo, and per the information contained in Attachment 1.

Zachary Helsley, Hossein Ashktorab, and Kirsten Struve were available to answer questions.

Public Comments:
None.

The Committee received the information, and noted the following:

- Director Beall noted support for a more aggressive approach to maximize potable and non-potable recycled water in the County.
- The Committee noted staff are currently working on the 2nd phase of the desalination project and an update will be provided at the next RWC meeting.

It was moved by Director Beall and seconded by Chairperson Estremera and unanimously carried as amended to recommend to Valley Water's Board a potable reuse goal of 24,000 Acre-feet per Year (AFY) by 2035 as well as a long-term vision to maximize water reuse in the county for inclusion in the Water Supply Master Plan 2050. This long-term vision includes additional potable and non-potable reuse, desalination, stormwater capture, and other alternative water sources.

4.5. Receive and Accept the 2024 Proposed Recycled Water Committee Work Plan, And Provide Feedback on Upcoming Discussion Items, and 2024 RWC Meeting Schedule.

Recommendation: Receive and accept the 2024 proposed RWC Work Plan, and provide feedback on upcoming discussion items and the 2024 RWC meeting schedule.

Kirsten Struve reviewed the information on this item, per the attached Committee Agenda Memo, and per the information contained in Attachment 2.

Kirsten Struve, Hossein Ashktorab, and Nicole Merritt were available to answer questions.

The Committee received the information, and noted the following:

- The Committee noted support of removing monthly updates on Item 1.2, the Update on Purified Water Program with the Cities of Palo Alto and Mountain View from the 2024 RWC Work Plan to be added back on as needed per any salt removal facility updates.
- The Committee noted support of notifying city staff of Director Beall's interest regarding stormwater to prepare for the upcoming Joint Recycled Water Policy Advisory Committee with the Cities of San Jose and Santa Clara.
- The Committee noted staff's upcoming desalination update at the next RWC meeting will have additional information to address the public's questions and concerns.
- The Committee confirmed support of the cancellation of the April 2024 RWC meeting per staff's request.

Director Beall left the meeting and did not return.

Public Comment:
None.

The Committee noted support of staff's recommendations and accepted the 2024 RWC Work Plan as amended per removal of monthly updates on Item 1.2 and the 2024 meeting schedule as amended per cancellation of the regular April 2024 meeting by consensus without official action.

5. CLERK REVIEW AND CLARIFICATION OF COMMITTEE REQUESTS:

This is an opportunity for the Clerk to review and obtain clarification on any formally moved, seconded, and approved requests and recommendations made by the Committee during the meeting.

None.

6. Adjourn:

6.1. Adjourn to Regular Meeting at 12:00 p.m. on April 24, 2024.

Chairperson Estremera adjourned the meeting at 1:10 p.m., to the regular meeting at 12:00 p.m. on May 22, 2024 per the Committee supporting the cancellation of the April meeting.

Nicole Merritt
Assistant Deputy Clerk II

Date Approved:



Santa Clara Valley Water District

File No.: 24-0432

Agenda Date: 5/22/2024

Item No.: 4.1.

COMMITTEE AGENDA MEMORANDUM Recycled Water Committee

Government Code § 84308 Applies: Yes No
(If "YES" Complete Attachment A - Gov. Code § 84308)

SUBJECT:

Receive Purified Water Program Update including Partnerships with the Cities of San Jose and Santa Clara and Provide Feedback.

RECOMMENDATION:

Receive an update and provide feedback on the following topics:

- A. Collaboration effort with cities of San Jose and Santa Clara
- B. Development of a roadmap
- C. Update on consultant agreements; and
- D. Outreach

SUMMARY:

A. Collaboration with cities

Valley Water staff has provided draft staff funding agreements to the Cities of San José and Santa Clara. The San José City Council has approved the budget proposal for new positions beginning next fiscal year to support development of a potable reuse project in collaboration with Valley Water. These positions will support and work with Valley Water over the next two years to develop needed agreements for both the demonstration facility and full-scale Direct Potable Reuse (DPR) facility. In addition, over the next three years, the staff will work on:

- Reviewing and commenting on necessary technical studies currently underway by Valley Water as well as additional future needed studies
- Reviewing conceptual designs and bid package for demonstration facility
- Supporting preparation of the feasibility study and grant applications
- Collaborating on the DPR regulatory requirements, including formation of a Direct Potable Reuse Responsible Agency
- Private activity analysis for Regional Wastewater Facility (RWF) bonds
- California Environmental Quality Act (CEQA) and, if needed, National Environmental Policy Act (NEPA) analysis (i.e. for federal grants)

- Facilitate planning approvals for the demonstration facility and learning center
- Collaborate on regulatory approvals
- Develop cost-effective waste management strategies including for Reverse Osmosis Concentrate

Valley Water would reimburse city staff work that supports the demonstration and full scale DPR facilities estimated at up to \$1 million per year. The capital funds allocated for this project starting next fiscal year by Valley Water will provide the needed funding. The City of Santa Clara will also be providing a budget proposal for up to \$350,000 to assist with the project.

In addition, City of San José staff and Valley Water are collaborating on the need for an access road to a future Microsoft data center which is planned on private property adjacent to the Silicon Valley Advanced Water Purification Center.

In addition, City and Valley Water staff have begun meeting with San Francisco Bay Regional Water Quality Control Board staff to develop a strategy for Reverse Osmosis Concentrate management from the facility in an environmentally protective manner.

B. Development of a roadmap

On December 6, 2023, the Joint Recycled Water Policy Advisory Committee (JRWPAC) requested staff to return with the roadmap, including mutual objectives, timelines and resources needed to complete agreements within two years by April 2024. Since then, staff from the Cities and Valley Waters have developed the roadmap as requested by the JRWPAC. As previously discussed, a Direct Potable Reuse (DPR) project will provide the most flexible approach to potable reuse and was selected as the preferred approach for collaboration between the Cities and Valley Water. As previously discussed, the first necessary step is development of a demonstration facility.

The Cities and Valley Water's short-term goal is development of the demonstration facility with the following mutual objectives:

- Enable regulatory approvals and permitting of a full-scale facility that protects public health and meets the DPR regulations
- Ensure the most cost-effective design by informing treatment process selection for the full-scale facility
- Develop institutional arrangements
- Provide operator training and certification as required by the DPR regulations
- Establish Public outreach and education by creating a Learning Center

Long term objective for Valley Water is to develop the maximum feasible size of potable reuse to secure the county's long term water supply while protecting public health and meeting all pertinent regulations. Additional joint objectives include:

- Valley Water supports the cities in securing long-term water supply from SFPUC, which would prevent the need to shift this demand to North County groundwater or other Valley Water

supplies

- Ensuring continued wastewater treatment plant permit compliance and resulting environmental protection of the San Francisco Bay.

Valley Water is evaluating future water supply needs for the county, including projected SFPUC supplies as part of the development of their long-term Water Supply Master Plan.

The following agreements that support the existing Silicon Valley Advanced Water Purification Center (SVAWPC) will be reviewed and amended as needed to enable the DPR Demonstration Facility:

- Integration Agreement
- Operations and Maintenance agreement
- Land Lease

Long-term agreements will be developed in parallel, including wastewater availability, operations and maintenance including RO concentrate management, and land lease. Valley Water will be assisting the cities in securing the long-term SFPUC supplies for their customers as described above.

C. Update to Consultant Agreements

Valley Water is currently processing a contract amendment with CDM Smith the Project Management Company (PMC) for the Purified Water Project (PWP) to provide project management services related to the San Jose Purified Water Project (SJPWP). The agreement is being amended to reflect changes to the PWP as directed by the Board of Directors at the February 27, 2024, meeting when the Palo Alto PWP was placed on the CIP unfunded list. The amendment will reflect the necessary changes to focus efforts on the SJPWP including both the Phase I San Jose Direct Potable Reuse (DPR) demonstration facility and future full scale DPR facility. Staff expects to bring the amendment to the CIP Committee meeting in early June 2024.

D. Outreach

In preparation for a Direct Potable Reuse facility in San José, staff continues to work with a consultant to update the outreach plan with strategies to align with the demonstration and full-scale facility project timeline. Once the agreements between the agencies are established, staff will collaborate with the agencies to develop and implement tailored outreach strategies for San José and Santa Clara communities.

As part of the planning for the demonstration facility, staff and consultants are working to determine the scope of a potential learning education center to create a space that could accommodate tours and events for interactive educational experiences. Education and awareness are key to ensuring overall public support of potable reuse and mitigating any potential opposition to the project.

Additionally, staff received approval from the Division of Drinking Water and the California Department of Public Health to distribute the bottled purified water from the Silicon Valley Advanced Water Purification Center for education purposes. Staff is working on a bottling storage, tracking and distribution plan that meets Water Code 13570.n.1-4. This milestone is critical to building public

awareness and acceptance of advanced purified water since studies show that “seeing is believing.”

Simultaneously, staff continues to implement countywide public outreach initiatives to build support for purified water in our county, which includes:

- Public Tour Program - Since March 1, staff hosted 463 visitors at the Silicon Valley Advanced Water Purification Center (SVAWPC), which included 4 public tours and 23 private tours with university students, water industry leaders, public officials, community organizations and classroom students from 5th-12th grade. Among the visitors were three senior community groups: Sons in Retirement (SIR), The Villages Study Group and The Forum Senior Living.
- Stakeholder Outreach - Staff continues to strengthen the relationship and connection with specific stakeholder groups, community leaders, and industry professionals. Staff hosted the Water Education for Latino Leaders Conference (WELL), at the Purification Center. Valley Water Board Director Estremera and City of San José Vice Mayor Kamei gave opening remarks before touring the facility. To reach colleges and universities, staff hosted the San Jose State University Chapter of the American Institute of Chemical Engineers and participated in San Jose State University's annual Earth Day celebration on April 18 which engaged with more than 200 students. Additionally, the California Water Environment Association also toured the SVAWPC. Staff also presented to 86 physicians at Kaiser Permanente as a part of Valley Water's speaker's bureau program.
- Collaboration Opportunities - Staff participated in a virtual community workshop hosted by San José's Fuse Fellow to Elevate Community Priorities on Water Conservation and Reuse on March 13, 2024. Participants were encouraged to brainstorm ways to reach the community on important topics that promote equity and inclusion.

At Valley Water's Direct Potable Reuse (DPR) Workshop on May 10, staff presented Valley Water's outreach initiatives and coordinated with the Santa Clara County Medical Association to present Valley Water's collaboration with local medical professionals.

ENVIRONMENTAL JUSTICE AND EQUITY IMPACT:

There are no environmental justice and equity impacts associated with this item.

ATTACHMENTS:

Attachment 1: PowerPoint

UNCLASSIFIED MANAGER:

Kirsten Struve, 408-630-3138



San José Purified Water Project

Recycled Water Committee

May 2024


Short Term Objective – Construct Demonstration Facility

- New regulations will require additional treatment processes and new institutional arrangements
- Demonstration facility is necessary first step to a full-scale project

Objectives of Demo Facility:



Regulatory
Permitting




Interagency
Agreements



Train
Operators



Operational
and Technical
Studies



Outreach and
Public Perception

Example Demonstration Facilities




City of San Diego Pure Water Program



Metropolitan Water District of Southern
California

Proposed Agreement Structures – two steps



Resources Needed – Cost

City of San José resource needs to support development of the DPR project:

- Estimated cost is up to \$1M per year for three years

City of Santa Clara

- Estimated cost is up to \$350,000 to support negotiations

Resources Needs: Scope

Over the next two years, these staff will work on:


- Modifying existing agreements for demonstration Facility and developing agreements for the Full-Scale Facility
- Develop necessary data/information for the Agreements

Resources Needed: Scope - continued

Over the next three years, these staff will work on:

- Current and future studies as well as feasibility study and grants
- Collaborating on the DPR regulatory requirements, including formation of a Direct Potable Reuse Responsible Agency
- Facilitate planning approvals for the demonstration facility and learning center
- Reviewing conceptual designs and bid package for demonstration facility
- Collaborate on regulatory approvals
- California Environmental Quality Act (CEQA) and, National Environmental Policy Act (NEPA) analysis
- Private activity analysis for Regional Wastewater Facility (RWF) bonds
- Develop cost-effective waste management strategies including for Reverse Osmosis Concentrate

Draft Timeline for DPR Project in San Jose



THIS PAGE INTENTIONALLY LEFT BLANK



Santa Clara Valley Water District

File No.: 24-0434

Agenda Date: 5/22/2024

Item No.: 4.2.

COMMITTEE AGENDA MEMORANDUM Recycled Water Committee

Government Code § 84308 Applies: Yes No
(If "YES" Complete Attachment A - Gov. Code § 84308)

SUBJECT:

Receive an Update on Valley Water's Efforts to Actively Engage in Direct Potable Reuse (DPR).

RECOMMENDATION:

Receive an update on DPR regulations and DPR Workshop.

SUMMARY:

Direct Potable Reuse regulations are currently near their final form and moving through the administrative steps which include:

- Review and Approval by the Office of Administrative Law
- Filing with the Secretary of State
- Signing of the regulations by the Secretary of State, making them effective

It is anticipated that the regulations would become effective in the early summer of 2024.

On May 10, 2024, Valley Water hosted a DPR workshop. The focus of the workshop was to bring together the experts in the field, including stakeholders, partners, and regulators, to examine the new rules, technical challenges and solutions, environmental considerations, and public concerns related to DPR, and to discuss future Valley Water DPR projects and regional partnerships. This item will provide an update on the workshop.

ENVIRONMENTAL JUSTICE AND EQUITY IMPACT:

There are no environmental justice and equity impacts associated with this item.

ATTACHMENTS:

None.

UNCLASSIFIED MANAGER:

Kirsten Struve, 408-630-3138

THIS PAGE INTENTIONALLY LEFT BLANK



Santa Clara Valley Water District

File No.: 24-0431

Agenda Date: 5/22/2024

Item No.: 4.3.

COMMITTEE AGENDA MEMORANDUM Recycled Water Committee

Government Code § 84308 Applies: Yes No
(If "YES" Complete Attachment A - Gov. Code § 84308)

SUBJECT:

Receive South Santa Clara County Water Reuse Collaboration Update and Provide Feedback.

RECOMMENDATION:

Receive an update and provide feedback on South Santa Clara County Water Reuse Collaboration.

SUMMARY:

In 2017, the Joint Water Resources Committee (JWRC) was established by Valley Water, City of Gilroy, and City of Morgan Hill to advance water recycling interests in South County; and included identifying future opportunities for purified and recycled water reuse and funding opportunities to advance water recycling. In 2021, the JWRC established a Technical Working Group (TWG) to evaluate future options to advance water reuse, and purified water production and distribution in South County. Since September 2021, the TWG has met monthly with technical staffs from Gilroy, Morgan Hill, and Valley Water to collaboratively discuss water reuse issues. The Recycled Water Committee (Committee) has since received updates on TWG activities in December, March, and September of 2022; April, August, and December of 2023; and January 2024.

This update will discuss the TWG's progress toward completing the 2024 South County Recycled Water Distribution Master Plan (2024 Plan) and comments received at the April 2024 JWRC meeting. The 2024 Plan provides an update to the 2015 South County Recycled Water Master Plan and presents a reprioritized capital improvement program. The 2024 Plan's primary goals were to:

1. Perform a capacity analysis and evaluation of the existing distribution system,
2. Provide recommendations for mitigating distribution system deficiencies and servicing short-term users,
3. Summarize Morgan Hill water reuse opportunities,
4. Update figures and tables representing the existing distribution system, current and future

customers, and proposed system improvements, and

5. Develop an updated capital improvement program for the short-term horizon (5-years) .

This update includes highlights on distribution master planning for the South County recycled water system, potential options to provide water reuse to Morgan Hill in the future, and recommended capital improvement projects to alleviate system deficiencies and promote expanded reuse in South County. This also includes feedback from our South County partners and comments from the TWRC's April 2024. Valley Water staff will finalize the draft 2024 Plan to include the comments and recommendations received from our partners and distribute a final 2024 Plan to the JWRC and Committee in the future.

Staff will conclude the South County Update with a discussion of our United States Bureau of Reclamation (USBR) planning grant to develop a South County Recycled Water System Feasibility Study. This feasibility exercise will expand upon previous master planning work to evaluate and prioritize water reuse opportunities for nonpotable and potable water recycling in South County. The feasibility study is a prerequisite to seek federal funding under the Title XVI grant program in the future.

ENVIRONMENTAL JUSTICE AND EQUITY IMPACT:

There are no environmental justice and equity impacts associated with this item.

ATTACHMENTS:

Attachment 1: PowerPoint

Attachment 2: Recycled Water Master Plan

UNCLASSIFIED MANAGER:

Kirsten Struve, 408-630-3138



Update on South Santa Clara County Water Reuse Collaboration

Recycled Water Committee
May 22, 2024


2024 Recycled Water Master Plan

- Recommendations to mitigate deficiencies,
- Analysis of the existing distribution system,
- Morgan Hill water reuse opportunities,
- Important planning figures and tables, and
- Capital Improvement Program (5-years).




Morgan Hill Reuse Options

- Direct Potable Reuse
- Non-Potable Reuse from SBWR
- Purification for Ground Water Recharge
- Purification for Surface Water Augmentation
- Recycled Water from SCRWA
- Purified Water from SCRWA



2024 Plan CIP Recommendations



Comments & Recommendations

- ❑ MH options are all expensive
- ❑ Now is the time to evaluate opportunities
- ❑ Financial and political challenges
- ❑ Editorial and Technical Remarks
- ❑ Planning expediency stressed




USBR Planning Grant

- Feasibility Study**
- Technical Support**
- South County partnership**
- Construction Funding**
- Study Schedule**





THIS PAGE INTENTIONALLY LEFT BLANK


MAY 2024

2024 South County Recycled Water Master Plan Update

g ilroy




**South County Regional
Wastewater Authority**

2024 SOUTH COUNTY RECYCLED WATER MASTER PLAN UPDATE

FINAL

May 2024

A K E L
ENGINEERING GROUP, INC.

May 1, 2024

Santa Clara Valley Water District
5750 Almaden Expressway
San Jose, CA 95118-3686

Attention: Mr. David Tucker, P.E.
Associate Engineer, Project Manager

Subject: 2024 South County Recycled Water Master Plan Update

Dear David:

We are pleased to submit this 2024 South County Recycled Water Master Plan Update. The report includes the following major tasks:

- Performing a capacity analysis and evaluation of the existing distribution system and improvement alternatives.
- Provide recommendations for mitigating existing distribution system capacity deficiencies and servicing the short-term users.
- Summarizing the Morgan Hill recycled water options.
- Developing mapping of the existing distribution system, customers, and proposed improvements.
- Developing an updated distribution system Capital Improvement Program (CIP) for a short-term horizon (5-yr).

We are extending our thanks to you and your staff, and to Saeid Vaziry, South County Regional Wastewater Authority; Chris Ghione, City of Morgan Hill Public Services Director; Karl Bjarke, City of Gilroy Interim Public Works Director; who's courtesy and cooperation were valuable components in completing this study and producing this report.

Sincerely,

AKEL ENGINEERING GROUP, INC.

Tony Akel, P.E., D.WRE
President



Acknowledgements

Valley Water Board of Directors

John L. Varela, District 1

Barbara Keegan, District 2

Richard Santos, District 3

Jim Beall, District 4

Nai Hsueh, District 5

Tony Estremera, District 6

Rebecca Eisenberg, District 7

Valley Water Management Personnel

Hossein Ashktorab, Ph.D, Recycled & Purified Water Manager

David Tucker, Associate Engineer

Kirsten Struve, Assistant Officer for Water Supply

South County Regional Wastewater Authority

Saeid Vaziry, Environmental Programs Manager

Jimmy Forbis, General Manager

City of Morgan Hill

Chris Ghione, Public Services Director, City of Morgan Hill

James Sylvain, Deputy Director of Utilities

Tanya Carothers, Environmental Programs Administrator

City of Gilroy

Karl Bjarke, Interim Public Works Director

Jeff Castro, Operations Supervisor

Valley Water
2024 South County Recycled Water
Master Plan Update

Table of Contents

	Page No.
1.0 PURPOSE AND SCOPE.....	1
2.0 RELEVANT DOCUMENTS	2
3.0 EXISTING AND PLANNED RECYCLED WATER DISTRIBUTION SYSTEM.....	2
3.1 EXISTING SYSTEM.....	3
3.1.1 <i>North System Distribution Pipelines</i>	3
3.1.2 <i>South System Distribution Pipelines (Pajaro River Pipeline)</i>	4
3.1.3 <i>Distribution System Pump Stations</i>	4
3.1.4 <i>Storage Tanks/Reservoirs</i>	5
3.2 PLANNED RECYCLED WATER SYSTEM (BASELINE SYSTEM)	5
4.0 OPERATIONAL CONSTRAINTS	6
4.1 DISTRIBUTION SYSTEM CONSTRAINTS.....	6
4.2 SCRWA WWTP On-SITE OPERATIONAL STORAGE CONSTRAINTS	7
5.0 SUPPLY ANALYSIS AND RECYCLED WATER DEMANDS.....	7
5.1 SUPPLY VS. DEMAND ANALYSIS	7
5.2 EXISTING RECYCLED WATER USER DEMANDS.....	8
5.3 POTENTIAL RECYCLED WATER USERS AND DEMANDS	8
6.0 HYDRAULIC MODEL UPDATE AND CALIBRATION.....	9
6.1 HYDRAULIC MODEL UPDATE	9
6.2 HYDRAULIC MODEL CALIBRATION	9
7.0 HYDRAULIC ANALYSIS AND USER OPTIMIZATION	9
7.1 DESIGN CRITERIA	10
7.2 EXISTING SYSTEM EVALUATION	10
7.3 EXISTING RECYCLED WATER USER OPTIMIZATION	11
7.4 BASELINE SYSTEM EVALUATION WITH OPTIMIZED OPERATIONS.....	11
7.5 NEAR-TERM USERS EVALUATION WITH OPTIMIZED OPERATIONS.....	12
7.6 CONCEPTUAL BASELINE SYSTEM BUILDOUT	12
8.0 RECYCLED WATER OPTIONS FOR MORGAN HILL	13
8.1 MORGAN HILL REUSE OPTIONS RELEVANT STUDIES.....	13
8.2 UPDATED MORGAN HILL REUSE OPTIONS.....	14
8.2.1 <i>Option 1a and 1b – Direct Potable Reuse</i>	14
8.2.2 <i>Option 2 – NPR+ from South Bay Water Recycling</i>	15
8.2.3 <i>Option 3 – Satellite Advanced Water Purification Facility for Groundwater Recharge (GWR)</i>	16

8.2.4	<i>Option 4 – Satellite Advanced Water Purification Facility for Surface Water Augmentation (SWA)</i>	16
8.2.5	<i>Option 5 – Pumping Recycled Water from SCRWA to a Morgan Hill Recycled Water System</i>	17
8.2.6	<i>Option 6 – SCRWA Advanced Water Purification Facility for Groundwater Recharge in Morgan Hill</i>	17
8.3	MORGAN HILL RECYCLED WATER OPTIONS COMPARISON	18
9.0	RECOMMENDED IMPROVEMENTS AND SYSTEM OPERATIONS.....	18
9.1	CONSTRUCTED BUT INACTIVE IMPROVEMENTS.....	18
9.2	RECENTLY CONSTRUCTED IMPROVEMENTS.....	19
9.3	NEAR-TERM IMPROVEMENTS	19
9.4	LONG-TERM IMPROVEMENTS (CONCEPTUAL)	19
9.5	OPERATIONAL IMPROVEMENTS	20
10.0	CAPITAL IMPROVEMENT PROGRAM (5-YR).....	20
10.1	COST ESTIMATE ACCURACY	20
10.2	COST ESTIMATE METHODOLOGY	21
10.2.1	<i>Unit Costs</i>	21
10.2.2	<i>Construction Cost Index</i>	22
10.2.3	<i>Estimating Contingency Allowance</i>	22
10.3.1	<i>Project Related Costs.....</i>	22
10.4	CAPITAL IMPROVEMENT PROGRAM	22
10.4.1	<i>Capital Improvement Costs</i>	22

Valley Water
2024 South County Recycled Water
Master Plan Update

Table of Contents (Cont'd)

Figures

- Figure 1 – Study Area
- Figure 2 – Existing System
- Figure 3 – Planned/Future Pipeline Improvements
- Figure 4 – Historical WWTP Influent and RW Production
- Figure 5 – Existing Users Monthly Demands
- Figure 6 – Existing User Hourly Demands, MDD
- Figure 7 – Existing Customer Connections
- Figure 8 – North System Demands
- Figure 9 – South System Demands
- Figure 10 – Potential Future Users
- Figure 11 – Hydraulic Model Calibration
- Figure 12 – Existing System Evaluation
- Figure 13 – Existing MDD Operations
- Figure 14 – Optimized MDD Operations
- Figure 15 – Baseline Improvements plus Optimization Evaluation
- Figure 16 – Optimized MDD Operations + Near Term Users
- Figure 17 – Near-Term Users Evaluation with Optimized Operations
- Figure 18 – Conceptual Baseline Buildout
- Figure 19 – Morgan Hill Recycled Water Option 1 - Direct Reuse
- Figure 20 – Morgan Hill Recycled Water Option 2 - NPR+
- Figure 21 – Morgan Hill Recycled Water Option 3 - GWR
- Figure 22 – Morgan Hill Recycled Water Option 4 - SWA
- Figure 23 – Morgan Hill Recycled Water Option 5 - RW from SCRWA
- Figure 24 – Morgan Hill Recycled Water Option 6 - AWPF Water from SCRWA for GWR

Tables

- Table 1 – Existing System Inventory
- Table 2 – Existing Recycled Water System Demands
- Table 3 – Potential Recycled Water Users
- Table 4 – Recycled Water System Criteria
- Table 5 – Morgan Hill Recycled Water Options
- Table 6 – Baseline System Improvement Summary
- Table 7 – Cost Estimating Criteria
- Table 8 – Capital Improvement Program

South County Recycled Water Master Plan Update

1.0 PURPOSE AND SCOPE

This 2024 South County Recycled Water Master Plan Update provides an update of the distribution system capacity evaluation component of the previous 2015 South County Recycled Water Master Plan (2015 Master Plan) prepared for Santa Clara Valley Water District (Valley Water) and the South County Regional Wastewater Authority (SCRWA) in May of 2016. Since the completion of the 2015 Master Plan, new pipelines have been constructed, customer usage has changed, and operation at the Wastewater Treatment Plant (WWTP) has become increasingly challenging during peak usage and the high demand season.

Purpose

This study provides an updated **distribution system capacity evaluation** to the 2015 South County Recycled Water Master plan, with a 5-year short-term planning horizon. It also provides a summary for the **Morgan Hill potential RW options**.

This project, located in South Santa Clara County in the City of Gilroy ([Figure 1](#)), consisted of updating and evaluating the short-term capacity requirements for the South County Recycled Water Distribution System. It is intended as an update superseding the capacity analysis from the 2015 Master Plan.

Scope

This report documents the following scope of work tasks:

- Updating the inventory of the existing South County recycled water pipelines.
- Documenting the existing and short-term users recycled water demands.
- Updating the short-term recycled water demand projections.
- Performing a capacity analysis and evaluation of the existing distribution system and improvement alternatives.
- Providing recommendations for mitigating existing distribution system capacity deficiencies and servicing the short-term users.
- Summarizing the Morgan Hill recycled water options.
- Developing detailed mapping of the existing distribution system, customers, and proposed improvements.
- Developing an updated distribution system Capital Improvement Program (CIP) for a short-term horizon (5-yr).

2.0 RELEVANT DOCUMENTS

The 2015 South County Recycled Water System Master Plan is the primary document that was updated in this effort. This section lists other relevant reports that were referenced during the completion of this recycled water master plan update to the 2015 Master Plan, along with a brief description of each document.

- **2020 Countywide Water Reuse Master Plan (2020 CoRe Plan).** This document was developed to identify opportunities for Santa Clara County to expand water reuse and improve water supply reliability. This plan included water reuse options for the North County (San Jose, Palo Alto, and Sunnyvale) and the South County (Morgan Hill, Gilroy)
- **2019 Sustainable Water Management Plan (2019 SWMP).** This document presents water supply alternatives available for the Llagas and Coyote Valley Groundwater Subbasins and included a qualitative analysis and ranking system to prioritize impacts for each project and the benefits for each alternative.
- **2015 South County Recycled Water Master Plan Update (2015 Master Plan).** This report was an update to the 2004 Master Plan and updated the existing recycled water demands, identified and prioritized future users, performed a hydraulic analysis, and prepared a capital improvement program to mitigate existing system deficiencies and serve future users.
- **2010 South County Recycled Water Pipeline Short-Term Phase 1, Planning Study Report (2010 Planning Study).** This document includes information for the updated potential future users list and contains updates to the 2004 Master Plan short term facilities.
- **2004 South County Recycled Water Master Plan (2004 Master Plan).** This report included the development of potential recycled water users and a hydraulic model of Valley Water's recycled water system. The hydraulic model was used to evaluate the existing recycled water system and recommended improvements to accommodate future growth.
- **2000 South Bay Water Recycling, Phase 2 Concept Design Report (2000 Design Criteria).** This document includes Valley Water's design criteria for the recycled water system facilities.

3.0 EXISTING AND PLANNED RECYCLED WATER DISTRIBUTION SYSTEM

This section documents the existing recycled water infrastructure including the distribution system pressure zones, pump stations, storage tanks and includes a brief description for the planned baseline system.

3.1 Existing System

The existing recycled water distribution system is comprised of two separate delivery systems: the North System and the South System (Pajaro River Pipeline). The system consists of approximately 91,300 linear feet (17.3 miles) of 8-inch to 36-inch diameter pipelines, a 4 million gallons per day (mgd) booster pump station, and a 1.5 million gallons (MG) off-site storage tank, and is supported by a 3 MG on-site reservoir, a 6.9 mgd pump station, and a 6.0 mgd pump station at the SCRWA WWTP shown graphically on [Figure 2](#) and documented in [Table 1](#).

3.1.1 North System Distribution Pipelines

The North System is comprised of two pressure zones and serves the existing recycled water customers north of the SCRWA WWTP. The North System Pressure Zones are documented on [Figure 2](#).

- **Pressure Zone 1:** This zone is pressurized by the Area 93 Pump Station at the WWTP and includes a 200 cubic feet (ft³) pressurized surge tank.

The existing pipeline alignment heads north from the WWTP along Engle Way with parallel 12-inch and 36-inch mains and east with a 12-inch main along Southside Drive to supply the Gilroy Shooting Range. The 12-inch main then follows the Miller Slough north to the Princevalle Drain flood control maintenance road. A 12-inch spur from this intersection supplies the Calpine Energy Center to the east.

From the Calpine Energy Center spur, the 12-inch main continues west along the Princevalle Drain to supply the McCarthy Business Park and United Natural Food. The 12-inch pipeline continues west to supply water to B&T Farms and then crosses under Highway 101. At Monterey Road and the Princevalle Drain, a 12-inch extension supplies water south to the Gilroy Sports Park. The 12-inch pipeline then continues west along the Princevalle Drain and crosses through Gilroy High School to supply water to Christmas Hill Park and ending at the Zone 2 Pump Station.

Construction of a 30-inch main from Southside Drive in Luchessa Avenue (and through the Glen Loma development) to Christmas Hill Pump Station is nearing completion. There is one section of pipeline in the Glen Loma Development along Luchessa Avenue between Miller Avenue and Vintner Court that is not constructed. Once this last section is constructed, the southern loop will be complete which will enhance the existing system operations.

- **Pressure Zone 2:** This zone is supplied by the Zone 2 Pump Station (Christmas Hill Park) located just west of Christmas Hill Park which pumps water to the 1.5 MG Hoylake Tank.

From the Zone 2 Pump Station a 14-inch pipeline parallels the Uvas Creek Preserve along Grenache Way. At Club Drive there is an 8-inch spur which has been used to temporarily

supply the Glen Loma Ranch Development with recycled water for grading and other construction activities. From Club Drive the 14-inch continues north-west to Santa Teresa Boulevard where the turnout is located for the Eagle Ridge Golf Course. From Santa Teresa Boulevard the 14-inch continues west where the pipeline splits to the north and west. The 12-inch north branch supplies water to the Gilroy Golf Course, a couple of HOA's, and City of Gilroy parks. The 14-inch west branch continues southwest along Club Drive and connects to the 1.5 MG Hoylake Tank.

3.1.2 South System Distribution Pipelines (Pajaro River Pipeline)

The majority of the South System is owned and maintained by SCRWA under joint operations since it primarily serves agricultural customers that pay Valley Water. The pipeline was installed for discharge to the river in case of an emergency (e.g. high inflow conditions and low recycled water demands), but SCRWA has never used it for such a purpose, and instead distributes recycled water year-round to agricultural customers south of the WWTP.

This system is pressurized by the Area 94 Pump Station which pumps into a 20-inch pipeline that heads south-west then south-east from the WWTP ([Figure 2](#)). The pipeline goes through a right-of-way in the SCRWA Farms Agriculture lands to the intersection of Bloomfield Avenue and Sheldon Avenue. A 22-inch, inner diameter main continues south-east for 700 feet and decreases in diameter to a 20-inch main which continues south-east to a discharge turnout located on the Pajaro River near the railroad tracks. Turnouts along this pipeline serve the San Felipe Farms.

3.1.3 Distribution System Pump Stations

The existing recycled water distribution system has three pump stations, documented on [Table 1](#), and summarized as follows:

- **Area 93 Pump Station (North System, Pressure Zone 1)**. The Area 93 Pump Station is located at the SCRWA WWTP at an elevation of 154 feet and is comprised of five pumps. Each of the five pumps has a variable frequency drive that provides up to 1,530 gallons per minute (gpm). Thus, the total existing capacity is 7,650 gpm and the firm capacity is 6,120 gpm. During peak months the pumps are generally operated to maintain approximately 95 pounds per square inch (psi) in the North System Pressure Zone 1.
- **Zone 2 Christmas Hill Pump Station (North System Pressure Zone 2)**. The Zone 2 Christmas Hill Pump Station is located west of Christmas Hill Park at an elevation of 222 feet and is comprised of three pumps. Each of the three pumps has a variable frequency drive that provides up to 1,375 gpm. Thus, the total existing capacity is 4,125 gpm and the firm capacity is 2,750 gpm. The pumps are generally operated by water levels in the Hoylake Tank that is located west of Santa Teresa Boulevard within the Eagle Ridge Golf Community.

The existing distribution system currently experiences high headlosses in the pipelines due to high water demands, resulting in low pressures near the Christmas Hill Pump Station. Due to the restrictions in the existing system (causing low pressures) this pump station's speed is operated between 65% to 85% in order to maintain a suction pressure of 20 psi.

- **Area 94 Pump Station (South System)**. The Area 94 Pump Station is located at the SCRWA WWTP at an elevation of 154 feet and is comprised of three pumps. Each of the three pumps has a variable frequency drive that provides up to 2,100 gpm. Thus, the total existing capacity is 6,300 gpm and the firm capacity is 4,200 gpm. When serving customers in the South System the pumps are generally operated with high head to maintain approximately 80-85 psi in the South System. During river discharge pumping, which generally does not occur, the pumps are operated with low head as high pressures are not required for river discharges.

3.1.4 Storage Tanks/Reservoirs

The existing distribution system has two storage tanks/reservoirs with a combined volume of 4.5 MG.

- **3.0 MG Reservoir at the SCRWA WWTP**. The 3.0 MG reservoir located at the SCRWA WWTP has a base elevation of 160 feet. This reservoir also has a return pump station with a capacity of 3 mgd, and which is used to drain the 3.0 MG reservoir. The same pipeline that is used to drain this reservoir is also used to fill it. Therefore, this critical reservoir operates by alternating between fill and drain mode but cannot do both at the same time. This reservoir is used to support the distribution system during peak demands, provides equalization of treatment flows at the WWTP, and the Area 93 and Area 94 Pump Stations both pump from this reservoir.

This critical reservoir operates by alternating between fill-and-drain cycles but cannot do both at the same time. Operational enhancements are recommended at this critical facility.
- **1.5 MG Reservoir in Pressure Zone 2 (North System)**. The Hoylake Tank is the second storage reservoir, and it is located in Zone 2 (North System). This tank is located at the end of Hoylake Court, has a capacity of 1.5 MG, and a base elevation of 385 feet. The Zone 2 Christmas Hill Pump Station is set to fill this tank based on the water levels.

3.2 Planned Recycled Water System (Baseline System)

The planned recycled water system (baseline) from the 2015 Recycled Water Master Plan was developed to mitigate the existing system deficiencies and to expand service to the most viable customers based on the market assessment that was performed. These planned and future alignments included in this distribution system capacity master plan are documented on [Figure 3](#).

The hydraulic analysis will focus on these pipelines and identify the potential customers in close proximity that could connect with minimal required infrastructure.

4.0 OPERATIONAL CONSTRAINTS

The South County recycled water system is operated by the South County Regional Wastewater Authority, and at the Wastewater Treatment Facility located in the City of Gilroy. Jacobs Solutions Inc. have been providing management and staffing assistance at the SCRWA Wastewater Treatment Facility for many years, and they were consulted during this study. This section documents the operational constraints observed by the system operators, and they include distribution constraints that are being mitigated by the large distribution main projects constructed by Valley Water, and on-site storage constraints experienced during peak season usage.

4.1 Distribution System Constraints

The distribution main constraints were identified in previous studies including the 2004 and 2015 South County Master Plans. The existing 12-inch main in the North System, Pressure Zone 1 experiences high headlosses during peak recycled water usage resulting in low pressures and restricted operations at the Christmas Hill Booster Station. Valley Water has been diligently working on resolving the distribution bottle necks and has completed several large diameter pipeline projects in 2023 with one near-term project in Glen Loma remaining to complete the pipeline project from the WWTP to the Christmas Hill Pump Station. SCRWA operational staff commented on the constraints as follows:

Valley Water is addressing the distribution constraints by completing several large diameter conveyance pipeline segments in the North System.

“The SCRWA recycled water system has evolved over the years. In the past 7 years, constraints on the system have also evolved. Early on the main constraint was being able to get water offsite. With the upgrades to SCRWA’s 93 pumpstation and flow meters, this constraint has been alleviated to some degree”. (SCRWA operations staff, 2022).

It should be noted that since Valley Water has been actively resolving the distribution system bottlenecks, staff will further experience enhanced operations.

4.2 SCRWA WWTP On-site Operational Storage Constraints

The SCRWA WWTP on-site operational storage constraints were identified in the 2015 South County Master Plan. These current constraints are related to recycled water delivery scheduling, chances of overlapping delivery hours, and the unpredictable nature of the users. Additional storage and pumping will alleviate the current on-site operational constraints. The projects to address these constraints have not been initiated, and they include on-site storage as well as updates to the booster station. SCRWA operations staff commented on this constraint as follows: *“Our main current constraints are storage and pumping capacity”*.

Additional storage and pumping capacity add resilience to the Recycled Water system operation and provide SCRWA operations staff with leverage to better serve existing and anticipated future customers.

Operations staff currently schedule all planned equipment maintenance activities during the low recycled water usage season (wet months). However, when issues arise during the dry season, and which require immediate repairs, they work harder to resolve the operational issue, and mitigate service interruptions.

“If an issue arises prior to refilling the reservoir, we work with the users to reduce their demand. This includes but is not limited to having farmers switch from recycled water to their well systems, shutting off Eagle Ridge Golf course (if their pond is full), reducing onsite usage, and working with other users as necessary to lower usage”. (SCRWA operations staff, 2022).

Additional storage and pumping capacity add resilience to the Recycled Water system and provide SCRWA operations staff more leverage to better serve existing and anticipated future customers.

5.0 SUPPLY ANALYSIS AND RECYCLED WATER DEMANDS

This section documents the recycled supply versus demand analysis, the existing and potential recycled water users, usage types, and diurnal patterns.

5.1 Supply vs. Demand Analysis

The recycled water system relies on water from the SCRWA Wastewater Treatment and Reclamation Plant, which collects and treats wastewater flows from the cities of Morgan Hill and Gilroy. Approximately 73% of the influent flows are from residential customers, 17% from commercial/institutional customers, and 10% are from industrial customers. **Figure 4** documents the monthly historical WWTP influent flow versus the recycled water production. Since 2017, the WWTP influent water has been trending down due to conservation measures and plumbing code changes, while the recycled water production has been trending higher.

The monthly recycled water usage is documented on [Figure 5](#) which identifies the recycled water use type (landscape irrigation, municipal and industrial (M&I), agriculture water (crop irrigation), and utility) by month (June 2021 to May 2022) as compared to the wastewater annual treatment plant influent flow. The WWTP influent average is approximately 6.1 mgd and the annual recycled water usage is 2.09 mgd, however during peak usage recycled water demands increase up to 5.7 mgd. The maximum day demands by hour are documented on [Figure 6](#), which shows peak recycled water use above the WWTP influent flows during high use periods. These peak flows have to be supplied by the existing 1.5 MG tank in Zone 2 and the 3.0 MG recycled water tank at the WWTP. There is approximately 0.4 mgd of surplus capacity for future users during peak summer months.

5.2 Existing Recycled Water User Demands

The existing recycled water users (meter locations) are identified on [Figure 7](#). The historical recycled water use has been generally consistent as documented on [Figure 4](#), with only a slight upward trend. Based on the historical recycled water production analysis, the existing recycled water demands for these users are based on the most recent monthly billing records from June 2021 to May 2022 and adjusted to the total recycled water production. These recent demands and allocation will provide the most up to date and accurate results for the hydraulic analysis. The annual recycled water use (including utility water) was approximately 2,338 AFY as documented on [Table 2](#).

The maximum day demands were developed based on peak month SCADA from the Area 93 and 94 pump stations and is estimated at 3,945 gpm as documented on [Table 2](#) (North System: 1,912 gpm and South System: 1,404 gpm). The peak hour demands were developed based on the reported hours of operation extracted from the yearly recycled water use permits that are submitted to SCRWA. [Figure 8](#) and [Figure 9](#) document the north and south system user demands diurnals.

5.3 Potential Recycled Water Users and Demands

The 2015 Recycled Water Master Plan included a thorough market assessment and customer ranking system for potential recycled water users. This capacity analysis focused on these high ranking and potential customers near the baseline system as identified on [Figure 10](#) and documented on [Table 3](#). The annual demands for each user were extracted from the 2015 Master Plan and the peaking factors developed from the updated existing system demand analysis were applied to determine the projected maximum day demands. The projected demand of the baseline potential users is approximately 4,529 gpm. Two potential long-term users were also included in this analysis, Gilroy Gardens and Western Tree and Nursery.

6.0 HYDRAULIC MODEL UPDATE AND CALIBRATION

The South County's recycled water distribution system hydraulic model combines information on the physical characteristics of the recycled water system (pipelines, pump, storage reservoirs) and operational characteristics (how they operate). The hydraulic model then performs calculations and solves a series of equations to simulate flows in pipes and calculate pressures at nodes or junctions. The recycled water model was developed using the water modeling software, InfoWater Pro by Autodesk, which offers an intuitive graphical interface and robust integration with ESRI's ArcGIS.

6.1 Hydraulic Model Update

The hydraulic model was updated to reflect current facility improvements and pipeline alignments based on recent construction. The existing water demands were also updated in the hydraulic model to reflect the most recent billing records and spatial allocation.

6.2 Hydraulic Model Calibration

Calibration is intended to instill a level of confidence in the pressures and flows that are simulated, and it generally consists of comparing model predictions to field measured results, and making necessary adjustments. The calibrated hydraulic model was updated with system operational controls, and was verified with Supervisory Control and Data Acquisition (SCADA) system data obtained for July 2021.

The model calibration consisted of comparing the pump flows from the Area 93 and Area 94 pump stations to SCADA for the summer months. [Figure 11](#) documents multiple peak use days from July 2021 (SCADA) as compared to the hydraulic model outputs. The demand allocation and diurnal patterns developed in the demand analysis resulted in an acceptable match between the SCADA and model outputs. The hydraulic model is now an established benchmark and can be used for system evaluations.

7.0 HYDRAULIC ANALYSIS AND USER OPTIMIZATION

The section documents the evaluation criteria utilized in the hydraulic analysis for the existing and planned baseline system and includes recommendations for system operations to optimize and maximize the capacity of the existing facilities and limited supply. The scenarios included in this analysis are as follows:

- **Existing System Evaluation:** This scenario evaluates the existing system (pre-2023) and recycled water usage to identify the deficiencies in the distribution system. This scenario does not include the recently constructed 30-inch Luchessa pipeline.
- **Existing Recycled Water User Optimization:** This scenario evaluates the existing system with optimized use of recycled water usage.

- **Baseline System Evaluation with Optimized Operations:** This scenario evaluates the existing system plus the recently constructed and near-term baseline system improvements with optimized operations.
- **Near-Term Users Evaluation with Optimized Operations:** This scenario evaluates the baseline system with additional users to maximize the available recycled water.
- **Conceptual Baseline System Buildout:** This scenario evaluates the conceptual buildout of the baseline system (included for long-range planning purposes only).

7.1 Design Criteria

Velocity, headlosses and pressures are important factors in the design of a recycled water distribution system. To properly serve customers, the velocities and headlosses need to be a reasonable and provide adequate pressure for customers.

The criterion used in the analysis of the recycled water system was originally obtained from the South Bay Water Recycling, Phase 2 Concept Design Report, dated February 2000. The criterion is intended for maintaining efficient system operation while providing a reliable service to the recycled water system customers.

Table 4 documents the criterion used for evaluating the capacity adequacy of the distribution system during peak day demands and peak hour demands.

Design Criteria

- Velocities less than 5 feet per second (fps).
- Headlosses less than 4 feet per 1,000 feet (ft/kft).
- Minimum Pressures at 35 pounds per square inch (psi).
- Operating pressures ranging between 60 and 120 psi (ideal).

7.2 Existing System Evaluation

The existing system evaluation was performed for the pre-2023 distribution system, and does not include the recently constructed 30-inch main in Luchessa Ave. This scenario highlights the system constraints operations staff have experienced in the previous few years.

The hydraulic analysis for the existing system identified numerous pipelines and pressures under the SCRWA criteria. The existing 12-inch main will experience headlosses up to 17 ft/1000ft (criteria is < 4 ft/1000ft). These high headlosses result with service pressures below the 35 psi minimum criteria (preferred 60-120 psi). As a result, the Christmas Hill booster station has to operate at a lower speed in order to maintain a suction pressure above 20 psi. The hydraulic analysis results are documented on **Figure 12**.

The existing system operations are documented on **Figure 13**. This figure documents the recycled water flow as compared to the system demands and the high peak demands that must be supplied by the existing tanks in order to meet the demands. The peak demands in the system are 9.2 mgd while peak flows from the WWTP are 7.5 mgd. Additionally, due to the low pressures at Christmas Hill booster station, the pump runs at a reduced capacity resulting with near constant flow during high demand periods to maintain the Hoylake Tank.

7.3 Existing Recycled Water User Optimization

During summer months the recycled water system experiences high peak usage due to the agricultural and irrigation uses. Being able to shift some of the water usage during peak hours to off-peak will ease the operations and depletion of the storage tanks.

Stantec was retained by SCRWA during this distribution system master plan update to perform a high-level analysis to identify opportunities for shifting demands during peak usage, and thus optimize the system operations. The approach of this optimization is summarized as follows:

- Step 1. Identify which users' "hours of use" can be shifted. Which users are not flexible, which are flexible.
- Step 2. Work with the "flexible" users to optimize the daily water use.

The existing user demands, and their current hours of operations are inventories on [Table 2](#). This information was provided to Stantec to review the permitted hours of operation, and the results of the high-level analysis provided by Stantec are summarized as follows:

"We have reviewed the data for each user and ... There are a lot of limitations with the users and why their hours cannot change. For the few users that have flexibility, the changes are very minor and therefore would not help to optimize the existing recycled water usage. We have talked about this with Valley Water staff as well and they agree any changes would be minor and not help to optimize the recycled water usage. There is potential to take the data ... provided into consideration when new users come online and set their hours of operation accordingly".
Stantec, 2023.

Operation limitations on the users' side indicate no flexibility in shifting the desired deliveries. Thus, the recycled water system's current operation is considered running at, or near, an optimized level.

Based on the results of this analysis the users' hours of operation will remain the same for the future system analyses.

7.4 Baseline System Evaluation with Optimized Operations

Valley Water is actively constructing several segments along the distribution system, which are intended to resolve existing bottlenecks and for future system expansion. The construction of the segments in the North System (baseline system) are occurring in difference phases, with some segments constructed but are currently inactive while others are under construction as documented on [Figure 3](#). The baseline improvements in this scenario include the 30-inch main from Southside Drive to the Christmas Hill booster station (P-1, P-2, P-4, plus the constructed but inactive mains) and the 18-inch main that links the new 30-inch main to the existing 12-inch main in Cameron Boulevard (P-3). Please note this segment (P-3) has not been constructed and may not since Valley Water has been unable to secure an easement.

With the construction and activation of the Baseline system improvements, pipeline headlosses are reduced resulting in higher and more adequate pressures experienced in Zone 1. These higher pressures allow the Christmas Hill booster station to operate at a higher capacity and allow for more optimized operations. With the higher suction pressures, Christmas Hill pumping capacity can be increased back to full capacity allowing for filling the

Hoylake Tank during off-peak hours. [Figure 14](#) documents

Baseline system with existing demands but with optimized operations. The peak hour flows are reduced from 7.5 mgd to 6.4 mgd which eases the stress on the WWTP operations and tank depletion.

The hydraulic analysis results for the Baseline system with optimized operations are documented on [Figure 15](#). The 14-inch discharge pipeline in Zone 2 had pipeline headlosses over criteria (up to 6.6 ft/kft), but system pressures and operations are not impacted.

Completing the imminent and near-term improvements will result with more adequate pressures in Zone 1, and more efficient and reliable operations at the Christmas Hill Booster Station.

7.5 Near-Term Users Evaluation with Optimized Operations

The near-term scenario includes two new potential users (Glen Loma and the Data Center) to maximize the use of the available recycled water. The selection of users presented here is speculative and actual potential customers will vary depending on their projected demands and interest in using recycled water. There is approximately 0.4 mgd of surplus capacity for future near-term users during peak summer months.

The hydraulic analysis utilized the optimized operations at Christmas Hill and is documented on [Figure 16](#). The hydraulic analysis results are documented on [Figure 17](#). The addition of these new users causes minor impacts to the baseline system but will increase the stress on the WWTP operations and reliance on WWTP on-site reservoir.

7.6 Conceptual Baseline System Buildout

The conceptual baseline buildout (long-term) scenario includes each of the potential future users from [Table 3](#). This scenario will require the following improvements:

- Zone 2 pipeline improvements (P-5, P-6)
- Pipe improvements to service the large users of Gilroy Gardens and Western Tree and Nursery on the west side of the system (LT-P-8, LT-P-9).
- A new booster station from Zone 2 to the new Zone 3.
- Booster station capacity upgrades at Area 93 and Christmas Hill.
- Additional storage in Zone 2.

System expansion for the baseline long-term users will require additional improvements to the existing distribution system.

The hydraulic analysis results are documented on [Figure 18](#). The Zone 2 pipeline improvements P5, and P-6 mitigate the high headlosses observed in the previous scenarios and the planned baseline improvements are adequate for the potential long-term demands.

Please note, this scenario is conceptual and is highly dependent on wastewater influent flow increases plus additional treatment capacity. The existing WWTP influent flow is approximately 6.1 mgd and the buildup demands in this scenario is 11.6 mgd. This buildup scenario is conceptual and included for long-range planning purposes only.

8.0 RECYCLED WATER OPTIONS FOR MORGAN HILL

There is currently no recycled water delivered within the City of Morgan Hill's service area, though delivering recycled water to Morgan Hill from the SCRWA WWTP and other sources has been considered in the 2015 Master Plan and in other feasibility studies. Morgan Hill has been consistently interested in exploring potential feasible opportunities where recycled water can be implemented in the future and added to their water supply portfolio. This section is intended to provide an updated summary of the currently considered six feasible reuse options.

Morgan Hill has been consistently interested in exploring potential opportunities to add water reuse to their supply portfolio. This section provides an update on six potentially feasible options.

8.1 Morgan Hill Reuse Options Relevant Studies

This section lists previous relevant reports and studies which explored the opportunities and potential costs of adding recycled water to the water supply portfolio in Morgan Hill.

- **2015 South County Recycled Water Master Plan Update.** The Santa Clara Valley Water District, the South County Regional Wastewater Authority, the City of Morgan Hill (Morgan Hill), and the City of Gilroy (Gilroy) partnered to explore the continued use, promotion, and expansion of the recycled water in the region. The agencies retained the services of Stantec and Akel Engineering Group to complete the 2015 South County Recycled Water Master Plan Update and which included a market assessment and developed project alternatives for expanding the existing recycled water system currently serving the City of Gilroy and adjacent County users. One of the considered alternatives included extending a recycled water pipeline from the SCRWA wastewater plant northward to service the City of Morgan Hill.
- **2016 Recycled Water Feasibility Evaluation.** With intent to provide more focus on the City of Morgan Hill recycled water needs, Morgan Hill retained the services of Akel Engineering Group and Stantec to further explore opportunities in recycled water for Morgan Hill, and to prepare the 2016 Recycled Water Feasibility Evaluation. This study identified potential recycled water users through a market assessment and included high

level costs for the potential alternatives. As identified in the market assessment, the potential future users of recycled water in the City include landscape irrigation, agricultural irrigation, industrial processes, and indirect potable reuse. As part of the 2016 RWFE, infrastructure required to convey recycled water from the South County Regional Wastewater Authority Wastewater Treatment Plant in the City of Gilroy to the potential users was identified.

- **2019 Sustainable Water Management Plan.** The 2019 Sustainable Water Management Plan, by Akel Engineering Group, Inc. was finalized in September 2019 for the cities of Morgan Hill and Gilroy. This plan documents the water supply alternatives analysis and project rankings for the Llagas Groundwater Subbasin and Coyote Valley. This report is intended to identify on-going and potential projects impacting the water supplies for the groundwater aquifers and includes a quantitative analysis to rank each alternative.
- **2020 Countywide Water Reuse Master Plan (2020 CoRe Plan).** This Countywide Water Reuse Master Plan (CoRe Plan) by Brown and Caldwell was finalized in June 2021. This countywide plan explores opportunities for reliable local water, imported water, and recycled water within Valley Water's service area. This report is intended to identify opportunities to expand water reuse throughout Valley Water's service area, including the City of Morgan Hill. The report identified three alternatives (options) with potential costs and risk levels, which are documented in this section.

8.2 Updated Morgan Hill Reuse Options

This section summarizes six potential recycled water options for the City of Morgan Hill. These six options were extracted from the following relevant studies, which were referenced in the previous section: *2020 Valley Water's Countywide Reuse Master Plan*, *2016 Recycled Water Feasibility Evaluation*, *2015 South County Recycled Water Master Plan Update*, and the *2019 Sustainable Water Management Plan*.

The six Morgan Hill reuse options were further refined and developed during discussions between Valley Water, Morgan Hill, and Gilroy. It should be noted that during peak recycled water usage there is no additional wastewater available for treatment. For this scenario, either reductions to existing users or additional storage would be required to supply recycled water.

8.2.1 Option 1a and 1b – Direct Potable Reuse

In December of 2023 the California State Water Resources Control Board adopted new regulations for direct potable reuse (DPR). While not explored in-depth in the CoRe Plan, direct potable reuse or the planned introduction of recycled water either directly into a public drinking water system, or into a raw water supply immediately upstream of a drinking water treatment plant may provide opportunity for a secure water source that can supply recycled water directly into the City of Morgan Hill's water system. Once the new regulations are finalized in 2024, water systems

will be able to submit plans for DPR for approval. Should DPR projects prove to be a feasible path in the future, the City of Morgan Hill could consider moving in that direction.

There are two likely options to deliver purified water to the Morgan Hill Water System ([Figure 19](#)): The 1a option consists of the development of a satellite wastewater treatment facility in combination with an Advanced Water Purification Facility (AWPF) that utilizes the City's wastewater. The 1b option consists of the construction of the AWPF at the South County Regional Wastewater Authority and pumping the treated water back to Morgan Hill.

Option 1a: Direct Potable Reuse via Treated Water Augmentation into water system (via Satellite WWTP and AWPF). This option would include a satellite WWTP and an AWPF.

Option 1b: Direct Potable Reuse via Treated Water Augmentation into water system (via purified water pumped from SCRWA). This option would include an AWPF at SCRWA, approximately 12 miles of 24-inch pipeline, and a pump station.

These options were not included in the CoRe Plan but a brief summary of benefits and limitations is provided as follows:

Benefits. *These options would require less pipeline infrastructure and have less operations and maintenance (O&M) costs than a satellite WWTP and AWPF. Provides a drought-resilient water supply for the City of Morgan Hill.*

Limitations. *There is a high cost of infrastructure which would be borne by Llagas subbasin unless there is grant funding, high O&M costs, and additional solids loading and reduced recycled water availability at SCRWA.*

8.2.2 Option 2 – NPR+ from South Bay Water Recycling

This option includes importing recycled water supplies from South Bay Water Recycling (SBWR) via 16 miles of 16-inch pipeline. A transmission main from SBWR would connect to a future recycled water distribution system in Morgan Hill. This option is documented on [Figure 20](#).

Benefits. *According to the 2020 CoRe Plan, this option would improve groundwater management (water supply reliability) for Morgan Hill by importing NPR+ supply from SBWR to serve non-potable demands in place of groundwater, which is currently the sole water source of Morgan Hill.*

Limitations. *According to the 2020 CoRe Plan, an agreement to establish terms of exporting SBWR NPR+ supply from San Jose and neighboring areas to Morgan Hill would be needed, as the existing Silver Creek Agreement between Valley Water and San José expires in 2027. Long-term supply reliability is unconfirmed. Operational impacts to the SBWR system have not been evaluated, and a new reservoir may be needed to supply reliable summertime flows. Valley Water may need to reassess the potential impacts of recycled water on the Llagas Subbasin prior to moving forward as there is potential for groundwater quality degradation*

from using recycled water for irrigation. Given shifting development trends in Morgan Hill, an updated NPR market assessment is needed. Additionally, without grant funding the cost would be borne entirely by Llagas subbasin for the operations and maintenance.

8.2.3 Option 3 – Satellite Advanced Water Purification Facility for Groundwater Recharge (GWR)

This option includes recharging the Llagas subbasin in the San Pedro Ponds with purified water, which would be produced at a satellite WWTP treating the City's wastewater and an AWPF. This purified water would be conveyed to San Pedro Ponds through 3 miles of 16-inch pipelines along Maple Avenue and Hill Road. This option is shown on [Figure 21](#).

Benefits. According to the 2020 CoRe Plan, this option would improve water supply reliability and drought resilience for Morgan Hill by recharging the Llagas Subbasin with purified water.

Limitations. According to the 2020 CoRe Plan, high unit costs with uncertain value to improving South County water supply reliability. Limited wastewater available for satellite treatment in Morgan Hill and relied upon for meeting existing South County Recycled Water System (RWS) demands. A Morgan Hill satellite facility would increase solids loads to SCRWA, posing operational issues that may be substantial. If implemented in Morgan Hill, solids handling requires further study and may increase costs significantly. Density and proximity of active private wells limit GWR locations in South County. San Pedro Ponds recharge facility is assumed the delivery point; which currently have significant recharge restrictions due to groundwater level issues/septic interference. Valley Water has recently finished a high-level feasibility study to identify alternatives to restore the capacity of these ponds, however conditions and reliability of increasing raw water delivery to Llagas Subbasin and specific recharge facility still need to be confirmed. A drought-resilient source of water would be ideal to combat droughts as Valley Water delivers raw water to all recharge facilities in Llagas Subbasin when supplies are available. Prolonged droughts impact the deliveries, albeit Valley Water does prioritize Morgan Hill facilities. Additionally, the assumed location for the evaporation pond for reverse osmosis concentrate management (ROC) in Gilroy gets inundated with stormwater (unsuitable for evaporation pond). New permits from Regional Board(s) and/or State Water Resources Control Board's Division of Drinking Water are also needed for discharging purified water.

8.2.4 Option 4 – Satellite Advanced Water Purification Facility for Surface Water Augmentation (SWA)

This option includes supplementing recharge of the Llagas Subbasin with water supplies provided by Valley Water, which would be delivered to ponds within the City's service area. In exchange for these water supplies, the City would deliver purified water delivered to Valley Water's Anderson Reservoir northeast of the City's service area. This option would include a satellite WWTP, an AWPF, and approximately 6 miles of 16-inch pipeline. This option is shown on [Figure 22](#).

Benefits. According to the 2020 CoRe Plan, this option would improve water supply reliability and drought resilience for Morgan Hill by recharging the Llagas Subbasin with raw water supplied from Valley Water via the Santa Clara Conduit in exchange for an equivalent amount of purified water delivered to Anderson Reservoir for SWA.

Limitations. According to the 2020 CoRe Plan, high unit costs with uncertain value to improving South County water supply reliability. Limited wastewater available for satellite treatment in Morgan Hill and relied upon for meeting existing South County RWS demands. Morgan Hill satellite facility would increase solids loads to SCRWA, posing operational issues that may be substantial. If implemented in Morgan Hill, solids handling requires further study and may increase costs significantly. New permits from Regional Board(s) and/or State Water Resources Control Board's Division of Drinking Water needed for discharging purified water to Anderson Reservoir. Conditions and reliability of increasing raw water delivery to Llagas Subbasin and specific recharge facility need to be confirmed.

8.2.5 Option 5 – Pumping Recycled Water from SCRWA to a Morgan Hill Recycled Water System

This recycled water option was extracted from the 2015 South County Recycled Water Master Plan Update and was also a high-ranking project in the 2019 Sustainable Water Management Planning study. This is identified as Alternative 1 or 2 in the 2015 SCRWMP Update and includes 9 miles of 24-inch transmission mains, 4 miles of distribution mains, and a pump station. This option would deliver recycled water from SCRWA to a recycled water system in the City of Morgan Hill. This option is shown on [Figure 23](#).

This option was not included in the CoRe Plan but a brief summary of benefits and limitations is provided as follows:

Benefits. This option would provide recycled water services to Morgan Hill and require less O&M costs than a satellite plant.

Limitations. This option has a high cost of infrastructure and there is currently no recycled water availability during peak usage periods. As with Option 2, Valley Water may need to reassess potential impacts of recycled water in the Llagas Subbasin prior to moving forward.

8.2.6 Option 6 – SCRWA Advanced Water Purification Facility for Groundwater Recharge in Morgan Hill

This recycled water option was also extracted from the 2015 South County Recycled Water Master Plan Update and was one of the highest high-ranking projects in the 2019 Sustainable Water Management Planning study. This option includes an AWPF at the SCRWA, 12-miles of 24-inch pipeline, and a pump station. This option would deliver purified water from SCRWA for groundwater recharge in the City of Morgan Hill. This option is shown on [Figure 24](#).

This option was not included in the CoRe Plan but a brief summary of benefits and limitations is provided as follows:

Benefits. *This option would provide recycled water for groundwater recharge in Morgan Hill.*

Limitations. *This option has a high cost of infrastructure which would be borne by Morgan Hill and Gilroy/Llagas subbasin if there is no grant funding.*

8.3 Morgan Hill Recycled Water Options Comparison

The six Morgan Hill reuse options are summarized on [Table 5](#), with a brief description, the amount of reuse augmentation added to the Morgan hill portfolio, the major infrastructure requirements, high-level opinion of conceptual project costs, likelihood of implementation, feasibility of implementation, advantages, and disadvantages.

It should be noted that the costs presented on [Table 5](#) were extracted from the relevant reports and may include varying levels of assumptions, cost estimate classification, cost accuracy, and contingencies. This study recommends these costs be further revisited and scrutinized for a more accurate and fair comparison of costs between the presented options.

When comparing the high-level opinion of conceptual costs, Option 2 (NPR+ from South Bay Water Recycling) seems to have one of the lowest implementation costs and highest feasibility ratings, however actual implementation requires negotiations and an agreement with the City of San José.

Newer technologies and recently adopted DPR regulations may unlock new options for the City of Morgan Hill in the future leading to Options 1a and 1b becoming more feasible. The City of Morgan Hill intends to continue to work in partnership with Valley Water to determine the best path forward to enhance its water supply and resiliency portfolio.

Morgan Hill intends to continue to work in partnership with Valley Water to determine the best path forward to enhance its water supply and resiliency portfolio.

9.0 RECOMMENDED IMPROVEMENTS AND SYSTEM OPERATIONS

This section provides a summary of the recommended recycled water distribution system improvements to mitigate existing capacity deficiencies and accommodate future system expansion within the City of Gilroy. The recommended improvements are shown on [Figure 3](#) and summarized on [Table 6](#). They are also described in this section.

9.1 Constructed but Inactive Improvements

These pipelines have been constructed but are currently inactive. There is approximately 13,650 feet of 30-inch main that can be activated once the remaining baseline system improvements in Zone 1 are constructed. These pipelines are highlighted in gray on [Figure 3](#).

9.2 Recently Constructed Improvements

- **P-1.** This 30-inch pipeline starts at Southside Drive, continues north through an agriculture right of way, and ends at Luchessa Avenue. This pipe is approximately 3,380 feet in length.
- **P-2.** This 30-inch pipeline starts at Luchessa Avenue and an agricultural right of way, continues west on Luchessa Avenue and ends at Greenfield Drive. This pipeline is approximately 10,270 feet in length.

9.3 Near-Term Improvements

- **P-3.** This 18-inch pipeline starts at Luchessa Avenue and an agricultural right of way, continues east on Luchessa Avenue turns north at Cameron Boulevard and ends at the Princevalle Drain. This pipeline is approximately 2,450 feet in length.
- **P-4.** This 30-inch pipeline starts at the roundabout intersection of Miller and Luchessa Avenue continues west on Luchessa Avenue, and ends at the roundabout intersection of Vintner Street and W Luchessa Avenue. This pipeline is approximately 715 feet in length.
- **WWTP-1.** This improvement is a 3 MG recycled water reservoir expansion at the WWTP.
- **WWTP-2.** This improvement is a recycled water pump station at the WWTP to aid in filling/draining of the on-site storage reservoir.
- **WWTP-3.** This improvement is for the on-site pipelines (approximately 1,500 feet) for the reservoir expansion and proposed pump station improvements.

9.4 Long-Term Improvements (Conceptual)

- **P-5.** This 24-inch pipeline starts at the Zone 2 pump station, continues west through the Home Ranch development, and ends at Uvas Creek. This pipeline is approximately 4,250 feet in length.
- **P-6.** This 24-inch pipeline starts at Uvas Creek, continues west on Santa Teresa Boulevard, and ends at Cobblestone Court. This pipeline is approximately 1,620 feet in length.
- **LT-P-8.** This 18-inch pipeline starts at the Meritance development, continues west in the Uvas Creek right of way and then south in the Gilroy Gardens Service Road, and ends at the new Zone 2 Tank/Zone 3 Booster Station. This pipeline is approximately 3,700 feet in length.

- **LT-P-9.** This 18-inch pipeline starts at the new Zone 2 Tank Site/Zone 3 Booster Station, continues west in the Gilroy Gardens right of way, and ends at Lake Kathryne. This pipeline is approximately 3,230 feet in length.
- **LT-T1.** This improvement is a new 1.5 MG storage reservoir in Zone 2.
- **LT-BS1.** This improvement is for a new 2,250 gpm total capacity Zone 3 booster pump station.
- **LT-BS2.** This improvement is for a Christmas Hill pump station capacity upgrade to 5.5 mgd (total).
- **LT-BS3.** This improvement is for an Area 93 pump station capacity upgrade to 9.3 mgd (total).

Please note that this Long-Term scenario is conceptual and is highly dependent on wastewater influent flow increases plus additional treatment capacity. The existing WWTP influent flow is approximately 6.1 mgd and the buildout demands in this scenario is 11.6 mgd.

9.5 Operational Improvements

Due to the existing system restrictions and storage constraints, the Christmas Hill pump station operates at a reduced flow to maintain adequate suction pressures and needs to operate almost 24/7 during high use periods ([Figure 13](#)). With the activation and construction of the recently constructed and Near-Term pipelines, the Christmas Hill pump station will be able to pump at its design capacity. This will allow operations to pump during off-peak hour to fill the Hoylake tank and ease the storage constraints at the WWTP ([Figure 14](#)).

10.0 CAPITAL IMPROVEMENT PROGRAM (5-YR)

This section provides a summary of the recommended domestic water system improvements costs. The section also presents the cost criteria and methodologies for developing the Capital Improvement Program.

10.1 Cost Estimate Accuracy

Cost estimates presented in the capital improvement program were prepared for general master planning purposes and, where relevant, for further project evaluations. The final costs of a project will depend on several factors including the specific project scope of work, costs of labor and material, and market conditions during construction.

AACE International (Association for the Advancement of Cost Engineering, International) has defined five estimate classes for general construction based on the maturity level of the project scope definition. These estimate classes are extracted from the *AACE International Recommended Practice No. 56R-08, Cost Estimate Classification System – As Applied in*

Engineering, Procurement, and Construction for the Building and General Construction Industries (Rev. August 2020) and briefly summarized on the following matrix.

Costs developed in this study should be considered “Class 5” and have an expected accuracy range of **-30 percent** and **+50 percent**.

Class	Description	Data Availability and Percent Accuracy
Class 5	This classification is also known as an order of magnitude estimate and is generally intended for long-range capital planning and master plans . This estimate is not supported with detailed engineering data about the specific project, and its accuracy is dependent on historical data and cost indices.	The data is 0% to 2% complete and includes the location and proposed project. It is generally expected that this estimate would be accurate within -30 percent to +50 percent .

10.2 Cost Estimate Methodology

Cost estimates presented in this section are opinions of probable construction and other relevant costs developed from several sources including cost curves, Akel experience on other master planning projects, and input from City staff. Where appropriate, costs were escalated to reflect the more current ENR (formerly Engineering News Record) Construction Cost Index (CCI). The ENR CCI is a cost estimating tool updated weekly, used by engineers to gage the current cost for new construction.

This section documents the unit costs used in developing the opinion of probable construction costs, the Construction Cost Index, and markups to account for construction contingency and other project related costs.

10.2.1 Unit Costs

The unit cost estimates used in developing the CIP are summarized in **Table 7**. The unit costs are intended for developing the Class 5, Order of Magnitude estimates, and do not account for site specific conditions, changes in labor or material costs during the time of construction, final project scope, implementation schedule, detailed utility and topography surveys, investigation of alternative routings for pipes, and other various factors. The CIP included in this report accounts for construction and project-related contingencies as described in this section.

10.2.2 Construction Cost Index

Costs estimated in this study are adjusted utilizing the ENR CCI, which is widely used in the engineering and construction industries.

The costs in this Water System Master Plan were calculated using a 20-City national average ENR CCI of 13,171, reflecting a date of August of 2022.

10.2.3 Estimating Contingency Allowance

Knowledge about site-specific conditions for each proposed project is limited at the master planning stage; therefore construction contingencies were used. In the absence of bid tabulations, the estimated construction cost includes a **20 percent** contingency allowance to account for unforeseen events and unknown field conditions.

10.3.1 Project Related Costs

The capital improvement costs also account for project-related costs, comprised of construction and administration. The construction costs contingency is comprised of engineering design, construction management, and inspection. In the absence of bid tabulations, the construction related costs were estimated by applying an additional **20 percent** to the baseline costs. The administration contingency costs are comprised of project administration (developer and City staff) and legal costs and are estimated by applying an additional **30 Percent** to the baseline.

10.4 CAPITAL IMPROVEMENT PROGRAM

This section documents the capital improvement program, including estimated costs.


10.4.1 Capital Improvement Costs

The Capital Improvement Program costs for the projects identified in this master plan update for mitigating existing deficiencies and for servicing potential future growth near the baseline system are summarized on **Table 8**. The Capital Improvement Program lists the type of improvement, location, and cost.

Each improvement was assigned a unique coded identifier associated with the improvement type and is summarized graphically on **Figure 3**.

**South County Recycled Water
Master Plan Update**

FIGURES



Legend

Morgan Hill to Gilroy System

- Future Relief Trunk
- Existing Relief Trunk
- Joint Trunk
- Existing Major Sewer Trunks

Recycled Water Distribution System Existing Features



Distribution Pipelines

City Limits Boundary

City Limits Area

Roads

PRELIMINARY

Updated: May 1, 2024

0 0.5 1 2 Mile


File Path: E:\xGlobe\Projects\SCVWWD\220714-RWSystem\Final\SCVWWD_Fig1_StudyArea_050124.mxd

70



Figure 1 Study Area

2024 South County Recycled Water
Master Plan Update
Santa Clara Valley Water District



Attachment 2

Page 32 of 64



Legend

Existing System

- WWTP
- Booster Station
- Storage Tank
- Pipes
- Constructed but Inactive
- Recent Construction
- Pressure Zone Boundary

Existing Features

- Rivers
- City Limits

Figure 2
Existing System
2024 South County Recycled Water
Master Plan Update
Santa Clara Valley Water District





Figure 3
Planned / Future Pipeline Improvements
2024 South County Recycled Water Master Plan Update
Santa Clara Valley Water District

Season	2015		2016		2017		2018		2019		2020		2021	
	WWTP Influent (mgd)	Recycled Water Production (mgd)												
Summer	5.7	2.9	6.1	2.6	6.3	2.7	5.9	2.8	6.1	2.7	6.2	3.3	6.0	3.4
Shoulder	5.9	2.2	6.3	1.9	8.1	1.6	6.4	1.7	7.2	1.6	6.5	2.0	6.1	2.2
Winter	6.0	1.5	6.2	1.2	8.3	1.1	6.1	1.2	6.7	1.4	6.2	1.4	6.3	1.3
Total	5.9	2.2	6.2	1.9	7.6	1.8	6.1	1.9	6.7	1.9	6.3	2.2	6.1	2.3






Figure 4
Historical WWTP Influent and RW Production
2024 South County Recycled Water Master Plan Update
Santa Clara Valley Water District

May 1, 2024





LEGEND

- WWTP Utility Water
- M&I
- Irrigation
- Agriculture
- Average Monthly Demand (Billing Records)

Figure 5
Existing Users
Monthly Demands
2024 South County Recycled
Water Master Plan Update
Santa Clara Valley Water District









Figure 6
Existing User Hourly Demands, MDD
2024 South County Recycled Water Master Plan Update
Santa Clara Valley Water District






North System Demands



North System (93) Pump Station Flows



LEGEND

- Christmas Hill Park - (North)
- Calpine Power Plant - Cogen
- McCarthy Business Park - NE
- United Natural Food
- B&T Farms (West)
- Tri Pointe (North)
- City of Gilroy Sports Park
- Gilroy Golf Course
- Heartland Owners Association (HOA) #8
- Trinchero Construction Company
- City of Gilroy #10
- City of Gilroy #7

- Christmas Hill Park - (Ranch)
- Calpine Power Plant - Peaker
- McCarthy Business Park - NW
- B&T Farms
- Gilroy Police Dept. Shooting Range
- Tri Pointe (South)
- Eagle Ridge Golf Course
- Heartland Owners Association (HOA) #1
- Heartland Owners Association (HOA) #11
- City of Gilroy #12
- City of Gilroy #9
- Santa Teresa & Third Street Park (City of Gilroy #6)


Figure 8 North System Demands

2024 South County Recycled
Water Master Plan Update
Santa Clara Valley Water District




May 1, 2024

South System Demands



South System (94) Pump Station Flows



LEGEND

- San Felipe Farms - Sheldon Turnout
- San Felipe Farms #135116
- San Felipe Farms #135115
- San Felipe Farms #135711

Figure 9 South System Demands

2024 South County Recycled
Water Master Plan Update
Santa Clara Valley Water District



May 1, 2024






Figure 10
Potential Future Users
2024 South County Recycled Water
Master Plan Update
Santa Clara Valley Water District

Valley Water

Attachment 2

Page 41 of 64





Legend

Peak Hour Pressures

- Greater than 100 psi
- 80 - 100 psi
- 60 - 80 psi
- 40 - 60 psi
- Less than 40 psi

Existing System

- WWTP
- Booster Station
- Storage Tank
- Pipes

Existing Features

- Rivers
- City Limits


Notes:

- Christmas Hill Pump Station flow limited due to low suction pressures caused by high pipeline headlosses
- Maximum Day Demand: 5.7 mgd
- Peak Hour Demand: 9.2 mgd
- Pipe flows and system pressures documented are during peak hour demands

Figure 12
Existing System Evaluation

2024 South County Recycled Water
Master Plan Update
Santa Clara Valley Water District

Existing Operations



LEGEND

- Zone 2 Demands
- South Demands
- Zone 1 Demands
- WWTP Utility Water
- X-Mas Hill PS Flow
- WWTP Influent (Avg.)
- Recycled Effluent
- North PS (Area 93) Flow
- South PS (Area 94) Flow


May 1, 2024

Figure 13
Existing MDD
Operations

2024 South County Recycled
Water Master Plan Update
Santa Clara Valley Water District



Optimized Operations with Pipeline Improvements



LEGEND

- Zone 2 Demands
- South Demands
- Zone 1 Demands
- WWTP Utility Water
- X-Mas Hill PS Flow
- WWTP Influent (Avg.)
- Recycled Water Effluent
- North PS (Area 93) Flow
- South PS (Area 94) Flow
- Existing Recycled Effluent

Notes:


1. Pipeline improvements include the Under Construction, Constructed but Inactive, and Imminent pipelines

May 1, 2024

Figure 14
Optimized MDD Operations

2024 South County Recycled Water Master Plan Update
Santa Clara Valley Water District





Legend

Peak Hour Pressures

- Greater than 100 psi
- 80 - 100 psi
- 60 - 80 psi
- 40 - 60 psi
- Less than 40 psi

Baseline System Improvements

- Pipelines
- Constructed but Inactive
- Recent Construction
- Near-Term Improvements

Existing System

- WWTP
- Booster Station
- Storage Tank
- Pipes

Existing Features


- Rivers
- City Limits

Notes:

- Christmas Hill Pump Station operates during off-peak hours
- Maximum Day Demand: 5.7 mgd
- Peak Hour Demand: 9.2 mgd
- Pipe flows and system pressures documented are during peak hour demands

Figure 15
Baseline Improvements Plus
Optimization Evaluation
2024 South County Recycled Water
Master Plan Update
Santa Clara Valley Water District

Optimized with Near Term Users



LEGEND

- Zone 2 Demands
- South Demands
- Zone 1 Demands
- WWTP Utility Water
- X-Mas Hill PS Flow
- WWTP Influent (Avg.)
- Recycled Effluent
- North PS (Area 93) Flow
- South PS (Area 94) Flow



Notes:

1. Pipeline improvements include the Under Construction, Constructed but Inactive, and Imminent pipelines
2. Near-Term users include Gilroy Data Center and Glen Loma

Figure 16
Optimized MDD Operations
+ Near Term Users
2024 South County Recycled
Water Master Plan Update
Santa Clara Valley Water District



May 1, 2024



Baseline System Improvements

- Tanks
- Pipelines
- Constructed but Inactive
- Recent Construction
- Near-Term Improvements

Existing System

- WWTP
- Booster Station
- Storage Tank
- Pipes

Existing Features

- Rivers
- City Limits

Notes:

- Christmas Hill Pump Station operates during off-peak hours
- Maximum Day Demand: 6.1 mgd
- Peak Hour Demand: 9.9 mgd
- Pipe flows and system pressures documented are during peak hour demands
- Near-Term users included are the Gilroy Data Center and Glen Loma

Figure 17
Near-Term Users Evaluation with Optimized Operations
2024 South County Recycled Water Master Plan Update
Santa Clara Valley Water District





Figure 18
Conceptual Baseline Buildout

2024 South County Recycled Water Master Plan Update
Santa Clara Valley Water District





Figure 19
Morgan Hill Recycled Water
Option 1 - Direct Reuse

2024 South County Recycled Water
Master Plan Update
Santa Clara Valley Water District






Legend

Raw Water System

- Existing SBWR Pipeline
- Proposed RW Pipeline
- Morgan Hill RW System
- Lakes
- City Limits

Figure 20
Morgan Hill Recycled Water Option 2 - NPR +
2024 South County Recycled Water Master Plan Update
Santa Clara Valley Water District



Legend

Water Purification System

- Water Purification Facility
- San Pedro Ponds
- Purified Water Pipeline
- Lakes
- City Limits

Source:
Countywide Water Reuse Master Plan (CoRe Plan), October 2020

Note:
• Satellite Advanced Water Purification Facility (AWPF) for Groundwater Recharge (GWR)

Figure 21
Morgan Hill Recycled Water Option 3 - GWR
2024 South County Recycled Water Master Plan Update
Santa Clara Valley Water District






Figure 22
Morgan Hill Recycled Water Option 4 - SWA
2024 South County Recycled Water Master Plan Update
Santa Clara Valley Water District



Legend

Option 5

- Booster Stations
- Recycled Water Recharge Pipeline
- Morgan Hill's Proposed RW System

Proposed

- Storage Tanks
- WWTP
- Booster Stations
- Baseline Improvements

Existing

- Recharge Ponds
- City Limits
- Roads
- Lakes
- Storage Tanks
- Booster Stations
- Recycled Water Pipelines

Updated May 1, 2024

File Path: \AKEL\Projects\SCVWD\220714-RWSystem\Final\SCVWD_Fig23-Option5_050124.mxd

92



Figure 23
Morgan Hill Recycled Water Option 5 - RW from SCRWA

2024 South County Recycled Water Master Plan Update
Santa Clara Valley Water District






Figure 24
Morgan Hill Recycled Water
Option 6 - AWPF Water
from SCRWA for GWR
2024 South County Recycled Water
Master Plan Update
Santa Clara Valley Water District



**South County Recycled Water
Master Plan Update**

TABLES

Table 1 Existing System Inventory

2024 South County Recycled Water Master Plan Update
Santa Clara Valley Water District

Pipes				
Pipe Diameter (in)		Length (ft)	Length (mi)	
North System				
8		750	0.1	
12		50,600	9.6	
14		11,750	2.2	
24		6,350	1.2	
30		1,400	0.3	
36		3,100	0.6	
Sub-Total		73,950	14.0	
South System				
10		350	0.1	
12		400	0.1	
20		15,650	3.0	
22		750	0.1	
30		200	0.0	
Sub-Total		17,350	3.3	
Total		91,300	17.3	
Booster Stations				
Booster Station ID	Pump No.	Head (ft)	Flow (gpm)	
North System				
Zone 1 Pump Station (Area 93)	1	295	1,200	
	2	295	1,200	
	3	295	1,200	
	4	295	1,200	
	5	295	1,200	
Total Capacity		6,000 gpm / 8.6 mgd		
Firm Capacity		4,800 gpm / 6.9 mgd		
Zone 2 Pump Station (Christmas Hill)	1	276	1,375	
	2	276	1,375	
	3	276	1,375	
	Total Capacity		4,125 gpm / 5.9 mgd	
	Firm Capacity		2,750 gpm / 4.0 mgd	
South System				
South Zone Pump Station (Area 94)	1	170	2,100	
	2	170	2,100	
	3	170	2,100	
	Total Capacity		6,300 gpm / 9.0 mgd	
	Firm Capacity		4,200 gpm / 6.0 mgd	
Tanks				
Tank ID	Height (ft)	Diameter (ft)	Volume (MG)	Base Elevation (ft)
WWTP Reservoir	22.5	150	3.0	160
North System Tank (Hoylake)	22.5	105	1.5	385

5/1/2024

Table 2 Existing Recycled Water System Demands

2024 South County Recycled Water Master Plan Update

Santa Clara Valley Water District

User No.	Customer Name	Meter Number	Usage Type	System	Zone ¹	Hours of Usage	Annual Demand ¹	Maximum Month Demand ²	Maximum Day Demand ³	Peak Hour Demand ^{4,5}
						(period)	(hrs)	(AFY)	(gpm)	(gpm)
Existing Users - North System										
1	Christmas Hill Park - (North)	893178	Irrigation	North	1	10pm - 7am	9	19.2	11.9	25.3
2	Christmas Hill Park - (Ranch)	70020157	Irrigation	North	1	10pm - 7am	9	10.6	6.6	12.4
3	Calpine Power Plant - Cogen	64897928	M&I	North	1	24hr	24	97.9	60.7	153.0
4	Calpine Power Plant - Peaker	61767407	M&I	North	1	24hr	24	4.6	2.9	9.7
5	McCarthy Business Park - NE	65660171	Irrigation	North	1	9pm - 7am	10	11.8	7.3	10.3
6	McCarthy Business Park - NW	64308108	Irrigation	North	1	9pm - 7am	10	0.0	0.0	0.0
7	United Natural Food SW	66435006	Irrigation	North	1	10pm - 7am	9	8.4	5.2	7.9
7a	United Natural Food SE	66435007	Irrigation	North	1	-	-	-	-	-
8	B&T Farms	904393	Agricultural	North	1	6am - 12pm and 4pm to 10pm	12	164.2	101.8	390.7
9	B&T Farms (West)	994024-8	Agricultural	North	1	6am - 12pm and 4pm to 10pm	12	67.3	41.8	116.9
10	Gilroy Police Dept. Shooting Range	60852362	Irrigation	North	1	7am - 11pm	16	0.2	0.1	0.1
11	City of Gilroy Sports Park	77132138	Irrigation	North	1	10pm - 7am	9	38.1	23.7	44.0
12	Eagle Ridge Golf Course	892545	Irrigation	North	2	6am - 2pm	8	532.3	330.0	515.4
13	Gilroy Golf Course	84633020	Irrigation	North	2	9pm - 6am	9	82.4	51.1	158.0
14	Heartland Owners Association (HOA) #1	78846906	Irrigation	North	2	10pm - 6am	8	2.2	1.3	5.2
15	Heartland West #8	64926314	Irrigation	North	2	10pm - 6am	8	7.3	4.5	6.7
16	Heartland Gardens #11	65939514	Irrigation	North	2	10pm - 6am	8	13.3	8.3	18.2
17	City of Gilroy #12	63267486	Irrigation	North	2	10pm - 7am	9	5.3	3.3	11.6
18	City of Gilroy #10	65939449	Irrigation	North	2	10pm - 6am	8	9.3	5.8	13.0
19	City of Gilroy #9	63267477	Irrigation	North	2	10pm - 6am	8	15.7	9.7	12.0
20	City of Gilroy #7	81877686	Irrigation	North	2	10pm - 6am	8	5.3	3.3	7.0
21	Santa Teresa & Third Street Park (City of Gilroy #6)	81877638	Irrigation	North	2	10pm - 6am	8	5.2	3.2	5.8
22	City of Gilroy #5	79448993	Irrigation	North	2	10pm - 6am	8	4.5	2.8	5.1
23	City of Gilroy #4	78255939	Irrigation	North	2	10pm - 6am	8	0.0	0.0	0.0
24	City of Gilroy #3	78846903	Irrigation	North	2	10pm - 6am	8	0.0	0.0	0.0
25	City of Gilroy #2	78293084	Irrigation	North	2	10pm - 7am	9	5.5	3.4	7.5
						Existing Users - North Subtotal	1,111	689	1,536	1,912
Temporary Construction Users - North System										
26	Overaa Construction	-	Construction	North	1	7am - 3:30pm	8.5	-	-	-
27	Tri Pointe (North)	1567721	Construction	North	1	7:30am - 5pm	9.5	1.8	1.1	1.1
28	Tri Pointe (South)	1590955	Construction	North	1	7:30am - 5pm	9.5	2.0	1.3	1.3
29	Trincherio Construction Company	A1068	Construction	North	2	7am - 3:30pm	8.5	0.9	0.6	0.6
						Existing Users - South Subtotal	266	165	587	1,404
WWTP Utility Water ⁶						24hr	24	961.2	597.0	716.0
						Total	2,338	1,450	2,838	3,945
										6,557

AKEL
ENGINEERING GROUP, INC.

5/1/2024

Notes:

1. Annual demands are based on monthly billing records from June 2021 to May 2022 and adjusted to production
2. Billing records from June 2021 to May 2022 were used to develop peak month factors for each user.
3. Maximum Day Demands were derived using SCADA from peak month of July to develop a MDD to MMD peaking factor for north and south users.
4. Peak hour demand was estimated using the formula PHD=(24/hours of permitted usage) x MDD
5. User peak hour demands are not additive, peak hour demand sub-totals and totals based on hours of operation
6. WWTP utility water historically peaks in the winter months, the MDD and PHD documented is based on max usage observed in SCADA from July 2021 (recycled water system maximum month).

Table 3 Potential Recycled Water Users

2024 South County Recycled Water Master Plan Update
Santa Clara Valley Water District

Customer Name ¹	Usage Type	System	Zone	Hours of Usage	Hours	Site Area (acres)	Average Demand ² (gpm)	Maximum Month Demand ³ (gpm)	Maximum Day Demand ³ (gpm)	Peak Hour Demand ⁴ (gpm)
Baseline System - Potential Users										
Gilroy Data Center	M&I	North	1	12am-12am	24	56.3	13.0	37.7	305.6	305.6
Glen Loma Ranch Development	Irrigation	North	1	10pm-7am	9	318.7	18.0	41.4	52.2	139.2
International Paper	M&I	North	1	8am-5pm	9	20.0	10.2	29.6	37.7	100.6
Vineyard Christian School	Irrigation	North	2	10pm-7am	9	3.3	4.0	9.2	11.6	30.9
Ascension Solorsano Middle School	Irrigation	North	1	10pm-7am	9	17.0	17.0	39.1	49.3	131.5
Gilroy Sports Park Expansion	Irrigation	North	1	10pm-7am	9	10.6	10.0	23.0	29.0	77.3
Gilroy Sports Park (Agriculture)	Agricultural	North	1	6am-5pm	11	5.7	21.0	75.6	113.4	247.4
Pacheco Pass Shopping Center	Irrigation	North	1	10pm-7am	9	67.0	3.4	7.7	9.7	25.9
Sydney Casper Park	Irrigation	North	1	10pm-7am	9	3.3	8.0	18.4	23.2	61.9
Syngenta	Irrigation	North	2	8am-5pm	9	29.1	12.0	27.6	34.8	92.8
Santa Teresa & Third Street Park	Irrigation	North	2	10pm-7am	9	2.2	8.0	18.4	23.2	61.9
City Park (Hecker Pass)	Irrigation	North	2	10pm-7am	9	2.0	8.0	18.4	23.2	61.9
Las Animas Elementary	Irrigation	North	1	10pm-7am	9	8.1	8.0	18.4	23.2	61.9
City Park (Santa Teressa Blvd and Club Drive)	Irrigation	North	2	10pm-7am	9	4.8	8.0	18.4	23.2	61.9
Cintas Corporation	M&I	North	1	24hr	24	2.2	74.0	214.6	273.8	273.8
Gilroy Gardens	Irrigation	North	2	10pm-7am	9	136.8	105.0	241.5	304.5	812.0
Western Tree Nursery	Irrigation	North	2	24hr	24	160.4	371.0	853.3	1,075.9	1,075.9
Gilroy High School	Irrigation	North	1	10pm-7am	9	55.4	48.0	110.4	139.2	371.2
Bonfante Nurseries	Agricultural	South	-	6am-5pm	11	44.9	133.0	478.8	718.2	1,567.0
Christopher Ranch	Agricultural	South	-	6am-5pm	16	149.4	233.0	838.8	1,258.2	1,887.3
Sub-Total							1,113	3,120	4,529	7,448
Long-Term Potential Users										
Gilroy Gardens	Irrigation	North	3	10pm-7am	9	136.8	105.0	241.5	304.5	812.0
Western Tree Nursery	Irrigation	North	3	24hr	24	160.4	371.0	853.3	1,075.9	1,075.9
Sub-Total							476	1,095	1,380	1,888
Total							1,589	4,215	5,910	9,336

A K E L
ENGINEERING GROUP, INC.

5/1/2024

Notes:

1. This table represents users within close proximity to existing recycled water pipelines and planned baseline system that have a potential for using recycled water
2. Average day demands were obtained from the 2015 South County Recycled Water Master Plan.
3. Maximum month and day peaking factors are based on billing records from June 2021 to May 2022 for similar use types (Ag, M&I, and Irrigation).
4. Peak hour demand was estimated using the formula PHD=(24/hours of permitted usage) x MDD

Table 4 Recycled Water System Criteria
 2024 South County Recycled Water Master Plan Update
 Santa Clara Valley Water District

Distribution System Performance Criteria	
Pipe Headloss	< 4 ft/kft
Pipe Velocity	< 5 fps
Minimum Pressure	35 psi
Normal Pressure Range	60 to 120 psi
Pump Station Performance Criteria	
Pressure Zone with Storage	Meet maximum day demand with largest unit out of service.
Pressure Zones without Storage	Meet peak hour demands with largest unit out of service.
Demand Peaking Factors	
Maximum Day Demand	
Agricultural Users	5.4 x ADD
M&I Users	3.7 x ADD
Irrigation Users	2.9 x ADD

5/1/2024

Table 5 Morgan Hill Recycled Water Options

2024 South County Recycled Water Master Plan Update

Santa Clara Valley Water District

Options ^{1,2,3}	Brief Description	Portfolio	Major Infrastructure	Costs ^{4,5}	Likelihood	Feasibility	Advantages	Disadvantages
1	2	3	4	5	6	7	8	9
Option 1	Option 1a: Direct Potable Reuse via Treated Water Augmentation into water system (via Satellite WWTP and AWPF)	1,100 - 2,900 AFY	Satellite WWTP and AWPF Facility	\$120M	Med./Low	Med./Low	- Less pipeline infrastructure required	- DPR recycled water regulations have not been adopted - High Cost of Infrastructure (satellite WWTP and AWPF) - Additional solids loading and reduced recycled water availability at SCRWA - High O&M Costs
	Option 1b: Direct Potable Reuse via Treated Water Augmentation into water system (via purified water pumped from SCRWA)	1,100 - 2,900 AFY	AWPF at SCRWA, 12 miles of 24-inch pipeline, pump station	\$150M	Med./Low	Med./Low	- Less O&M costs than a satellite WWTP/AWPF	- Current recycled water regulations - High Cost of Infrastructure (AWPF, pipelines, and pump station) - Additional solids loading and reduced recycled water availability at SCRWA
Option 2	NPR+ from South Bay Water Recycling	Delivers 2,900 AFY of NPR+ from SBWR to a new Morgan Hill recycled water system	16 miles of 16-inch pipeline	\$80M	Med./Low	Med.	- Availability of Water - Less O&M costs than a satellite plant and AWPF - Lowest cost opportunity	- Requires agreement with San Jose - High Cost of Infrastructure - Potentially high cost of water due to long distance pumping
Option 3	Satellite Advanced Water Purification Facility (AWPF) for Groundwater Recharge (GWR)	Delivers 1,900 AFY from a Morgan Hill 2.5-mgd satellite WWTP and 2.1-mgd AWPF to recharge facilities in Morgan Hill for GWR	Satellite WWTP and AWPF Facility 3 miles of 16-inch pipeline	\$140M	Low	Low	Groundwater recharge in Morgan Hill	- High Cost of Infrastructure (satellite plant, AWPF, and pipelines) - Inability to meet existing Customer demands during peak demand periods - Inadequate flow in sewer collection system could create odor and clogging problems - Resulting sludge loading and reduced flow could substantially change composition of WWTP influent potentially leading to compliance issues - High O&M Costs
Option 4	Satellite Advanced Water Purification Facility (AWPF) for Surface Water Augmentation (SWA)	Delivers 1,900 AFY from a Morgan Hill 2.5-mgd satellite WWTP and 2.1-mgd AWPF to Anderson Reservoir for SWA	Satellite WWTP and AWPF Facility 6 miles of 16-inch pipeline	\$160M	Low	Low	Surface Water Augmentation in Anderson Reservoir	- High Cost of Infrastructure (satellite plant, AWPF, and pipelines) - Inability to meet existing Customer demands during peak demand periods - Inadequate flow in sewer collection system could create odor and clogging problems - Resulting sludge loading and reduced flow could substantially change composition of WWTP influent potentially leading to compliance issues - High O&M Costs
Option 5	Pumping Recycled Water from SCRWA to a Morgan Hill Recycled Water System (RW Master Plan - Alt 1 or 2)	Delivers 3,000 AFY NPR water from SCRWA to Morgan Hill	9 miles of 24-inch pipeline, 4 miles of distribution pipelines, pump station	\$75M	Low	Med./Low	- RW Service to Morgan Hill - Less O&M costs than a satellite plant	- High Cost of Infrastructure (Pipelines, and Pump Station) - Availability of RW during peak usage
Option 6	Pumping Recycled Water from SCRWA to Morgan Hill for Groundwater Recharge (RW Master Plan - SCVWA IPR to Butterfield)	Delivers 3,000 AFY of AWPF water from SCRWA for IPR in Butterfield Channel	AWPF at SCRWA, 12 miles of 24-inch pipeline, pump station	\$146M	Low	Med./Low	RW Groundwater recharge in Morgan Hill	- High Cost of Infrastructure (AWPF, Pipelines, EIR, CalTrans Permits for crossing Hwy 101, and a Pump Station)

Notes:

1. Option 1a and 1b are potential future options depending on changes in the recycled water regulations

2. Options 2, 3, 4 were extracted from the 2020 Countywide Water Reuse Master Plan (CoRe Plan)

3. Options 5 and 6 were extracted from the 2019 Sustainable Water Management Plan

4. Costs documented have been escalated to April 2023 (ENR 13230)

5. Costs for each option are order of magnitude. Cost information for Options 1a, 2, 3, and 4 are based on the CoRe Plan and Options 1b, 5, and 6 are based on the 2015 Recycled Water Master Plan

5/1/2024

Table 6 Baseline System Improvement Summary

2024 South County Recycled Water Master Plan Update

Santa Clara Valley Water District

Scenario	Demands		Distribution System Improvement Summary
	Maximum	Day (mgd)	
Existing	5.7 mgd		-
Baseline System: Imminent -Term	5.7 mgd		<p>Imminent Term Distribution System Improvements:</p> <ul style="list-style-type: none"> Recent Construction: 13,650 feet of 30-inch diameter pipeline Constructed but Inactive: 6,120 feet of 30-inch diameter pipeline 770 feet of 16-inch diameter pipeline 640 feet of 12-inch diameter pipeline
Baseline System: Near - Term	6.1 mgd		<p>Near-Term Distribution System Improvements:</p> <ul style="list-style-type: none"> 715 feet of 30-inch diameter pipeline 2,450 feet of 18-inch diameter pipeline <p>Planned WWTP Recycled Water Projects:</p> <ul style="list-style-type: none"> Reservoir Expansion (Additional 3 MG) New Reservoir Pump Station 1,500 feet of on-site piping
Conceptual Baseline Buildout: Long - Term ¹	11.7 mgd		<p>Long-Term Distribution System Improvements:</p> <ul style="list-style-type: none"> 5,870 feet of 24-inch diameter pipeline 6,930 feet of 18-inch diameter pipeline New 1.5 MG Zone 2 Tank New 1,500 gpm (Firm) Zone 3 Pump Station Christmas Hill Pump Station Capacity Upgrade to 5.5 mgd Area 93 Pump Station Firm Capacity Upgrade to 9.3 mgd

Notes:

5/1/2024

1. Long-Term recycled water usage dependent on wastewater influent flow increase plus treatment capacity

Table 7 Cost Estimating Criteria

2024 South County Recycled Water Master Plan Update

Santa Clara Valley Water District

Pipe Size (Inner Diameter)		Unit Costs¹
	(in)	(\$/lineal foot)
	8	187
	10	211
	12	253
	14	283
	16	304
	18	312
	24	400
	30	500
	36	560
Pump Stations		
Pump Station Within WWTP or Upgraded Capacity at Existing Site		
Estimated Pumping Station Project Cost = $1.2 * 10^{(0.7583 * \log(Q) + 3.1951)}$; where Q is in gpm		
New Pump Station Outside WWTP		
Estimated Pumping Station Project Cost = $2.4 * 10^{(0.7583 * \log(Q) + 3.1951)}$; where Q is in gpm		
Storage Reservoirs (\$/gal)		
Earthwork, Lined and Covered Storage Pond		\$0.25
Steel Tank - Above Ground		
≤ 1.0 MG		\$2.69
1.1 MG - 3.0 MG		\$2.15
3.1 MG - 5.0 MG		\$1.55
> 5.0 MG		\$1.16
Costs Estimating Contingencies²		
Estimating		20%
Construction		20%
Administration		30%

AKEL
ENGINEERING GROUP, INC.

Notes:

1. Construction costs estimated using August 2022 ENR CCI of 13,171.
2. Contingencies:
 - Estimating contingency of 20% to account for unforeseen events and unknown conditions.
 - Construction contingency of 20% to account for engineering design and construction management and inspection.
 - Administration contingency of 30% to account for administration and legal costs.

5/1/2024

Table 8 Capital Improvement Program

2024 South County Recycled Water Master Plan Update
Santa Clara Valley Water District

Itemized Cost Estimate													
Improvement Number	Pressure Zone	Type of Improv.	Street	Limits	Pipeline and Appurtenances Costs				Baseline Construction Cost (\$)	Estimating Contingency Cost ³ (\$)	Construction Contingency Cost ⁴ (\$)	Administration Contingency Cost ⁵ (\$)	Total Estimated Capital Cost (\$)
					Diam. (in)	Length (ft)	Unit Cost ² (\$)	Pipe Cost (\$)					
Recent Construction Improvements													
Distribution System													
P-1	North - Zone 1	Pipe	Through Agriculture Fields ROW	Southside Dr. to Luchessa Ave.						Cost extracted from bid tabs - Phase 1B, 2A, 2B			
P-2	North - Zone 1	Pipe	Luchessa Avenue	Agriculture ROW to Greenfield Dr						21,300,000			
										Recent Construction Subtotal 21,300,000			
Near-Term Improvements													
Distribution System													
P-3	North - Zone 1	Pipe	Luchessa Avenue/Cameron Boulevard	Luchessa Ave to Princevalle Drain						Cost extracted from bid tabs - Phase 1C			
P-4	North - Zone 1	Pipe	Luchessa Avenue	Miller Avenue to Vintner Street						1,700,000			
										See Note 6			
										Distribution System Subtotal 2,970,000			
Other On-Site WWTP Recycled Water Projects													
WWTP-1	WWTP	Lined Reservoir ¹	Recycled Water Reservoir Expansion (Additional 3 MG)		3.0 MG				2,060,000	412,000	412,000	618,000	3,500,000
WWTP-2	WWTP	Pump Station ¹	New Reservoir Pump Station						815,000	163,000	163,000	244,500	1,390,000
WWTP-3	WWTP	Pipe	On-Site Pipelines						500,000	100,000	100,000	150,000	850,000
										WWTP On-Site Subtotal 5,740,000			
										Near-Term Subtotal 8,710,000			
Long-Term Improvements													
Distribution System													
P-5	North - Zone 2	Pipe	ROW through Home Ranch Development	Zone 2 Pump Station Outlet to Uvas Creek	24	4,250	400	1,700,000	1,700,000	340,000	340,000	510,000	2,890,000
P-6	North - Zone 2	Pipe	Santa Teresa Boulevard	Uvas Creek to Cobblestone Ct	24	1,620	400	648,000	648,000	129,600	129,600	194,400	1,100,000
LT-P-8	North - Zone 2	Pipe	Uvas Creek ROW/Gilroy Gardens Service Rd	Meritage Loop to New Zone 2 Tank Site/Zone 3 PS (Elev. 383)	18	3,700	312	1,154,400	1,154,400	230,880	230,880	346,320	1,960,000
LT-P-9	North - Zone 2	Pipe	Gilroy Gardens ROW	New Zone 2 Tank Site/Zone 3 PS to Lake Kathryn	18	3,230	312	1,007,760	1,007,760	201,552	201,552	302,328	1,710,000
LT-T1	North - Zone 2	Tank ¹	Gilroy Gardens	Zone 2 Storage Expansion		1.5 MG		3,225,551	3,225,551	645,110	645,110	967,665	5,480,000
LT-BS1	North - Zone 3	Pump Station ¹	2 x 750 gpm Duty + 750 gpm Standby		2,250 gpm (total)			1,310,000	1,310,000	262,000	262,000	393,000	2,230,000
LT-BS2	North - Zone 2	Pump Station ¹	Christmas Hill Capacity Upgrade		5.5 mgd (total)			978,390	978,390	195,678	195,678	293,517	1,660,000
LT-BS3	North - Zone 1	Pump Station ¹	North (Area 93) Recycled Water Pump Station Upgrade		9.3 mgd (total)			1,457,121	1,457,121	291,424	291,424	437,136	2,480,000
										Long-Term Subtotal 19,510,000			
Capital Improvement Summary													
Note:													
1. Tank and pump station pricing can vary widely with site conditions.													
2. Cost estimates are based on the Engineering News Record (ENR) construction cost index (CCI) of 13171 for the 20 cities for August 2022.													
3. Baseline construction cost plus 20% to account for unforeseen events and unknown conditions (Estimating Contingency).													
4. Baseline construction cost plus 20% to cover other costs including: engineering design, construction management, and inspection (Construction Contingency).													
5. Baseline construction cost plus 30% to account for project administration (developer and City staff) and legal costs (Administration Contingency).													
6. Improvement P-4 cost extracted from the Canyon Creek Recycled Water Pipeline Alignment Study by Kennedy Jenks, April 2024.													
										Recent Construction: 21,300,000			
										Immediate and Near-Term Subtotal: 8,710,000			
										Estimated Total: 49,520,000			



Santa Clara Valley Water District

File No.: 24-0149

Agenda Date: 5/22/2024

Item No.: 4.4.

COMMITTEE AGENDA MEMORANDUM Recycled Water Committee

Government Code § 84308 Applies: Yes No
(If "YES" Complete Attachment A - Gov. Code § 84308)

SUBJECT:

Receive the Desalination Engineering Feasibility Study Update.

RECOMMENDATION:

Receive update on the procurement process for a desalination engineering feasibility study and discuss next steps.

SUMMARY:

At the October 27, 2023, Recycled Water Committee (Committee) meeting staff presented an update on the completion of an Environmental Feasibility Study for the development of a desalination project in the Santa Clara County. The completion of this preliminary study was the first phase in evaluating a potential desalination project in the county. As discussed at the October meeting and at the direction of the Committee, staff is currently procuring a consultant to conduct the second phase, an engineering feasibility study which will evaluate the engineering feasibility, costs and regulatory permitting requirements associated with a desalination project in the South San Francisco Bay (South Bay). At the committee meeting, public outreach was also recommended for inclusion in the scope. This is the first time Valley Water is evaluating a desalination facility in the South Bay as an alternative water supply. A desalination project is also included for evaluation in the Water Supply Master Plan update for 2050.

On January 2, 2024, Valley Water issued a request for qualifications (RFQ) to conduct a Desalination Engineering Feasibility Study (DEFS) for a desalination project in the South Bay. Valley Water received three proposals for this RFQ and interviewed all three firms. The evaluation panel selected one firm and has finalized the contract negotiations with this firm. The contract agreement is currently in the legal review process with legal staff and staff plans to bring the contract agreement to the full Board of Directors at the June 11, 2024, meeting. The scope of services for this contract includes the following key tasks:

- Conduct feasibility of a desalination facility to produce potable water to augment existing Valley Water's water supplies as projected in the 2050 Water Supply Master Plan.

- Conduct fatal flaw analysis to screen alternatives identified in Environmental Feasibility Study
- Evaluate subsurface intakes, brine management.
- Evaluate transmissivity and groundwater hydraulic gradients (i.e. pumping/tidal flux) and water quality
- Conduct fatal flaw analysis of subsurface intakes, source water availability for a minimum 10 million gallons per day (MGD) production facility (20 MGD intake).
- Evaluate potential hybrid option using both subsurface and open intakes.
- Evaluate brine management (blending ratios, hydrodynamic mixing zones, dilution factors, RPA analysis, horizontal levee or other nature-based systems, qualitative impacts to water treatment plant outfalls in the SF Bay).
- Work with stakeholders to help identify possible siting locations (City of San José, City of Palo Alto, Regional Water Board, etc.)
- Assess geotechnical conditions.
- Determine technology options based on water quality, intake options, brine management and siting options.
- Facility siting and sizing evaluation
- Evaluate distribution system connection points, storage and in-situ instrumentation.
- Scalability evaluation
- Provide cost estimate for both capital and operating costs for most viable option.
- Greenhouse gas emissions and energy consumption evaluation for most viable option
- Applicability of CEQA and other regulatory requirements
- Supplemental Services may include stakeholder meetings, public outreach, conceptual design (<10%) and other tasks as needed.

The timeline for this study is estimated at one year following notice to proceed. The committee will be kept up to date at key milestones.

ENVIRONMENTAL JUSTICE AND EQUITY IMPACT:

There are no environmental justice and equity impacts associated with this agenda item.

ATTACHMENTS:


Attachment 1: PowerPoint

UNCLASSIFIED MANAGER:

Kirsten Struve, 408-630-3138

Desalination Engineering Feasibility Study

- RFQ Issued January 2, 2024
- Three firms selected for interviews
- Firm selected and currently finalizing agreement
- Anticipated contract approval by BOD June 2024
- Notice to proceed expected June 2024
- Project duration 12 months
 - 50% Progress Report: December 2024
 - CEQA and Regulatory Requirements Evaluation: March 2025
 - 80% Progress Report: April 2025
 - Fatal Flaw and Alternatives Analysis: May 2025
 - Final Report: June 2025
 - Share finding with RWC July 2025



THIS PAGE INTENTIONALLY LEFT BLANK



Santa Clara Valley Water District

File No.: 24-0237

Agenda Date: 5/22/2024

Item No.: 4.5.

COMMITTEE AGENDA MEMORANDUM Recycled Water Committee

Government Code § 84308 Applies: Yes No
(If "YES" Complete Attachment A - Gov. Code § 84308)

SUBJECT:

Receive Update on Bottling Purified and Water Tasting Station at the Silicon Valley Advanced Water Purification Center.

RECOMMENDATION:

Receive information on efforts to bottle advanced purified water for demonstration and outreach purposes.

SUMMARY:

In 2018, staff began development of an outreach program that would allow the Santa Clara Valley Water District (Valley Water) to bottle advanced purified demonstration water and evaluate on-site purified water taste testing for future education and outreach purposes (Purified Bottled Water Program). A technical work group (TWG) was formed to review existing purified demonstration water practices statewide and evaluate bottling purified water opportunities.

Assembly Bill 2022 (AB2022) authorizes an operator of an advanced water purification facility to cause advanced purified demonstration water to be bottled and distributed for educational and outreach purposes to promote water reuse.

In 2019, the TWG prepared an Implementation Plan for Bottling Purified Demonstration Water that addressed regulatory requirements, infrastructure improvements, testing and monitoring, regulatory engagement, communication, schedule, and resource requirements. Staff from the State Water Resources Control Board Division of Drinking Water (DDW) reviewed and provided recommendations for technical studies to support bottling approval.

The project faced significant delays due to COVID-19 impacts on supply chains, staffing transitions, and unforeseen health and safety constraints.

Following improvements to pilot scale treatment processes, including upgrades to plumbing, chemical dosing systems, and addition of online monitoring systems, staff carried out validation

testing of water purification equipment to demonstrate the facility's ability to produce advanced purified demonstration water. The results were summarized in an Advanced Oxidation Process Validation Report (Validation Report), which was subsequently approved by DDW in January 2023.

Building on results from the Validation Report, staff prepared a comprehensive Operations Plan for Bottling Advanced Purified Demonstration Water (Operations Plan), which detailed administrative processes, operational strategies and limits, and water quality testing that would ensure the safe and consistent production of advanced purified demonstration water in compliance with requirements in AB2022. The Operations Plan was approved by DDW in September 2023.

Staff has brought regular updates to the Recycled Water Committee throughout the project. Staff first brought the concept of bottling purified water to the Committee in August 2018, presented the draft Implementation Plan in July 2019, provided an update on implementation progress in June 2021 and February 2022, provided an update on the development of a Validation Test Plan in August 2022, and presented the completion of validation testing and received feedback of the bottle label in May 2023.

In October 2023, Valley Water successfully produced approximately 2,000 gallons of advanced purified demonstration water at the Silicon Valley Advanced Water Purification Center, using a combination of the processes at the facility and additional pilot scale treatment processes. The advanced purified demonstration water was produced according to procedures detailed in the approved Operation Plan, and the water was tested for all analytes with maximum contaminant levels (MCLs), analytes with California Notification Levels (NLs), pathogens (including E. coli, enteric virus, cryptosporidium, and giardia), and constituents of emerging concern identified in the State's Recycled Water Policy. The water quality testing showed that the advanced purified demonstration water met all federal and state drinking water standards.

In January 2024, staff submitted a summary report detailing the operational conditions which produced the advanced purified demonstration water and the subsequent results of water quality testing. Final approval to distribute bottles of advanced purified demonstration water for education and outreach purposes was provided by California Department of Public Health (CDPH) on March 29, 2024.

As specified in AB2022, 1,000 gallons of advanced purified demonstration water were bottled, resulting in approximately 16,000 8oz bottles. These bottles have a shelf life of approximately two years and will become an integral part of education and public outreach efforts to build support for Valley Water's purified water projects. Valley Water has now become the first agency in California to produce bottles of purified water with the new bottling regulations.

ENVIRONMENTAL JUSTICE AND EQUITY IMPACT:

There are no environmental justice and equity impacts associated with this agenda item.

ATTACHMENTS:

Attachment 1: PowerPoint

UNCLASSIFIED MANAGER:

Kirsten Struve, 408-630-3138

Update on Bottling Purified Water at the Silicon Valley Advanced Water Purification Center

Recycled Water Committee

May 22, 2024


Purified Demonstration Water

2

- AB2022 allows bottling of “advanced purified demonstration water” for outreach and educational purposes:**
 - Treated by microfiltration, reverse osmosis, advanced oxidation
 - Meets state and federal drinking water standards
- Restrictions:**
 - 1,000 gallons per year
 - 8 oz servings

Timeline

3



Bottles are ready!

4



- 16,000 bottles are ready for distribution to support education and outreach efforts

What's Next

- Bottles will be incorporated as an important part of our purified water education and outreach program
- New DPR Regulations require higher levels of treatment and will preclude future bottling
 - DPR Demonstration Facility could allow for bottling opportunities in the future



THIS PAGE INTENTIONALLY LEFT BLANK



Santa Clara Valley Water District

File No.: 24-0433

Agenda Date: 5/22/2024

Item No.: 4.6.

COMMITTEE AGENDA MEMORANDUM Recycled Water Committee

Government Code § 84308 Applies: Yes No
(If "YES" Complete Attachment A - Gov. Code § 84308)

SUBJECT:

Receive an Update on Federal and State Grant Opportunities for Recycled Water Projects.

RECOMMENDATION:

Receive an update on federal and state grant opportunities for recycled water projects.

SUMMARY:

As requested by the Recycled Water Committee, staff is providing another update on existing recycled water funding at the federal and state level. The last funding update was provided last August, and the information remains largely the same.

There is one new federal piece of legislation that if passed, will provide additional federal funding for large-scale water recycling projects. The bill authored by Congresswoman Grace Napolitano from Southern California aims to reauthorize the Large-Scale Water Recycling Program for six years, authorize \$1 billion in appropriations, and increase the minimum project cost for eligible projects from \$500 million to \$1 billion.

At the state level, two climate resilience bond measures are moving through the legislative process proposing about \$15 billion each: AB 1567 (Garcia) and SB 867 (Allen), which include funding for water, wildfire, flood protection, heat mitigation, clean energy, and workforce development. Both measures currently include \$300 million for water recycling.

Available Sources of Federal Funding

There are two main sources of federal funding available for recycled water projects nationwide, both of which are administered by the US Bureau of Reclamation (Reclamation):

- Title XVI (16) Water Reclamation and Reuse Program
 - Provides competitive grant funds to projects with a maximum award of \$30M
 - Typically only receives around \$65M in annual appropriations
 - Very high demand for this program

- Large-Scale Water Recycling Program
 - Brand new program created under the Bipartisan Infrastructure Law to fund large projects - those with a minimum cost of \$500M
 - No specific award cap, but the federal investment maxes out at 25% of the project cost
 - Received \$450M under the Bipartisan Infrastructure Law
 - Reclamation issued a rolling Notice of Funding Opportunity (NOFO) for construction under the Large-Scale Water Recycling Program in September 2023. A total of \$180M is available under this NOFO, which is open through November 2024. Eligible projects include planning, design, and construction of water reclamation and reuse facilities that have a completed Title XVI feasibility study submitted to Reclamation for their review and approval.

Current Funding Outlook

- Staff is developing a financial assistance strategy for the San Jose Purified Water Project (SJ PWP) that will grant support for the design and construction of a demonstration facility initially, followed by grant support for the design and construction of full-scale Direct Potable Reuse (DPR) facilities in San Jose.
- Staff will present this demonstration facility as Phase I of the larger, full-scale project so that we can be eligible for construction funding under the large-scale water recycling program.
- Staff has submitted a request for \$3M in Congressionally Directed Spending for the purified water demonstration facility. These funds would cover Valley Water's pre-design and environmental work in federal fiscal year 2025. These requests are very competitive and the timeline for the awards is uncertain given the unpredictability of the federal appropriations process.

Pending Legislation

- Congresswoman Grace Napolitano from Southern California has introduced a bill to reauthorize the Large-Scale Water Recycling Program for six years, authorize \$1B in appropriations, and increase the minimum project cost for eligible projects from \$500M to \$1B. Without reauthorizing the program, it will expire when the Bipartisan Infrastructure Law expires in 2026.
- Valley Water works closely with our coalition partners (WateReuse, Association of California Water Agencies, American Water Works Association, and more) at the federal level to seek increased funding for both water recycling programs and authorize new grant programs.

Available Sources of State Funding

There is one source of funding for recycled water projects at the state level, which is the State Water Resources Control Board (State Water Board) Water Recycling Funding Program (WRFP).

- Water Recycling Funding Program

- Maximum grant funding awards of \$15M.
- Maximum planning grant \$500K.
- Funded through the general fund and state bond initiatives.
- Overly prescribed due to pending applications of over \$5 billion as of August 2023.

Current Funding Outlook

- In FY 2023-24, the State Water Board had approximately \$231.4 million in grant funds and approximately \$21.7 million in loan funds available for WRFP construction projects.
- Governor's Proposed January Budget for FY 2024-25, proposed a reduction of \$174.4 million, with an additional \$100 million slated for delay until FY 2025-26. These adjustments are subject to negotiation with the legislature and subject to adoption before the end of session. The proposed cuts were not included in early budget actions, which cut \$17 billion (AB 106, Gabriel).
- If the proposed reduction and shift in funding are adopted, the available grant funds would be limited to approximately \$41.5 million, significantly lower than the total grant funds required to support pending construction project applications.

Pending Legislation - Climate Resilience Bonds

- Two climate resilience bond measures moving through the legislative process proposing about \$15 billion each: AB 1567 (Garcia) and SB 867 (Allen), which include funding for water, wildfire, flood protection, heat mitigation, clean energy, and workforce development. Both measures currently include \$300 million for water recycling.
- Valley Water is working with member organizations, such as WateReuse California, the Association of California Water Agencies, and the California Municipal Utilities Association, to advocate for a significant increase in recycled water funding to at least \$1 billion, with \$500K for potable reuse.
- Legislative leaders have indicated the state has a capacity to bond about \$20 billion. With three potential bonds for housing, education, and climate resilience competing for state borrowing capacity, legislative leaders have signaled that each bond should be about \$6 billion.

ENVIRONMENTAL JUSTICE AND EQUITY IMPACT:

There are no environmental justice and equity impacts associated with this item.

ATTACHMENTS:

Attachment 1: PowerPoint

UNCLASSIFIED MANAGER:

Marta Lugo, 408-630-2237

THIS PAGE INTENTIONALLY LEFT BLANK



**Federal and State Grant Opportunity Updates
Recycled Water Committee
May 2024**

Pending Federal Legislation

- The Large-Scale Water Recycling Reauthorization and Investment Act of 2024,
 - Reauthorize the Large-Scale Water Recycling Program for six years
 - Authorize \$1B in appropriations
 - Increase the minimum project cost for eligible projects from \$500M to \$1B.
 - Without reauthorizing the program, it will expire when the Bipartisan Infrastructure Law expires in 2026.

State Recycled Water Funding Cuts

3

- Water Recycling Funding Program
 - Maximum grant funding awards of \$15M.
 - Maximum planning grant \$500K.
 - Overly prescribed due to pending applications of over \$5 billion as of August 2023.
 - Governor's Proposed January Budget for FY 2024-25, proposed a reduction of \$174.4 million, with an additional \$100 million delayed until FY 2025-26.
 - Cuts would reduce funding to \$41 million.

State Climate Resiliency Bonds

4

- AB 1567 (Garcia) and SB 867 (Allen)
 - \$15 billion for water, wildfire, flood protection, heat mitigation, clean energy, and workforce development.
 - Both measures currently include \$300 million for water recycling.
 - VW advocating for \$1 billion for recycled water, with \$500K for potable reuse projects.
 - Climate resilience bond size expected to be lower.



Valley Water

Clean Water • Healthy Environment • Flood Protection

THIS PAGE INTENTIONALLY LEFT BLANK



Santa Clara Valley Water District

File No.: 24-0491

Agenda Date: 5/22/2024

Item No.: 4.7.

COMMITTEE AGENDA MEMORANDUM Recycled Water Committee

Government Code § 84308 Applies: Yes No
(If "YES" Complete Attachment A - Gov. Code § 84308)

SUBJECT:

Receive and Discuss the 2024 Recycled Water Committee (RWC) Work Plan, and Provide Feedback on Upcoming Discussion Items, and Upcoming Meeting Date.

RECOMMENDATION:

Receive information on the 2024 RWC Work Plan, and provide feedback on upcoming discussion items and next meeting date.

SUMMARY:

Under direction of the Clerk, Work Plans are used by all Board Committees to increase Committee efficiency, provide increased public notice of intended Committee discussions, and enable improved follow-up by staff. Work Plans are dynamic documents managed by Committee Chairs and are subject to change.

At the March 27, 2024 meeting, the Committee approved the 2024 work plan that has agenda items necessary for the continuation of the recycled water projects. An updated 2024 work plan (Attachment 1) proposes changes for the remaining meetings in the year.

Staff solicits Committee feedback on any additional timeline information for holding discussions on the assigned Work Plan items, confirmation of the next meeting dates, and would like to request canceling the June 2024 meeting.

ENVIRONMENTAL JUSTICE AND EQUITY IMPACT:

The review and acceptance of the RWC Work Plan and meeting schedule are not subject to environmental justice analysis.

ATTACHMENTS:

Attachment 1: 2024 Revised RWC Work Plan

UNCLASSIFIED MANAGER:

Candice Kwok-Smith, 408-630-3193

THIS PAGE INTENTIONALLY LEFT BLANK

RWC 2024 WORK PLAN

Task	Agenda Item	January	February	March	April	May	June	July	August	September	October	November	December
FY 24 Tactic 1: Advance the Purified Water Program													
1.1	Update on Purified Water Program including Partnership with Cities of San Jose and Santa Clara - Phase I Facility and full-scale Direct Potable Reuse Facility at the Silicon Valley Advanced Water Purification Center	X	X	X		X	X	X	X	X	X	X	X
FY 24 Tactic 2: Implement the Countywide Water Reuse Master Plan.													
2.1	Joint Mtg Prep/Debrief: Joint Recycled Water Policy Advisory Committee, including coordination on the Silicon Valley Advanced Water Purification Facility and building strong collaborative relationships	X		X									
2.2	Joint Mtg Prep/Debrief: Cities of Palo Alto/Mtn View.												
2.3	Joint Mtg Prep/Debrief: City of Sunnyvale.												
2.4	Update on SFPUC/BAWSCA Collaboration Efforts.												
2.5	Independent Advisory Panel.												
FY 24 Tactic 3: Continue to actively be involved with Direct Potable Reuse (DPR) guidance and implement actions for the future.													
3.1	Actively Engage in Direct Potable Reuse												X
FY 24 Tactic 4: Develop a Comprehensive Water Reuse Agreement for South County to advance water reuse and its production, distribution, and wholesaling in South County.													
4.1	South Santa Clara County Water Reuse Collaboration.	X											X
FY 24 Tactic 5: Continue to monitor feasibility of desalination.													
5.1	Continue to investigate feasibility of desalination (local and regional).												X
Others													
6.1	Regional discussion on options: Feasibility analysis of Recycled Water Exchange with Contra Costa Water District and Central Contra Costa Sanitary District.												
6.2	Update on Bottling Purified and water tasting station at the SVAWPC.												
6.3	Investigating Different Source of Water for Purification including Urban Water Runoff/Stormwater												
6.4	Outreach Comprehensive Efforts.												
6.5	Potential Water Reuse Goal based on Water Supply Master Plan	X		X									
6.6	State and Federal Grant opportunities												

*Blue strikes - items added on updated work plan

*Red strikes - items deleted from current work plan

THIS PAGE INTENTIONALLY LEFT BLANK