



Photo Credit: Dave Giordano  
Ecositemedia.com



# Imported Water Supplies 2022 Water 101 Academy

May 2022



# State and Federal water supplies

- State Water Project (SWP)
  - Operated by CA DWR
  - 1961 First deliveries to Santa Clara County
  - Contract amount: 100,000 AF
  - Est. long-term average deliveries: 55,000 AF
- Central Valley Project (CVP)
  - Operated by USBR
  - 1987 First deliveries to Santa Clara County
  - Contract amount: 152,500 AF
  - Est. long-term average deliveries: 110,000 AF

# State and Federal water supplies


- State Water Project (SWP)
  - Operated by CA DWR
  - 1961 First deliveries to Santa Clara County
  - Contract amount: 100,000 AF
  - Est. long-term average deliveries: 55,000 AF
- Central Valley Project (CVP)
  - Operated by USBR
  - 1987 First deliveries to Santa Clara County
  - Contract amount: 152,500 AF
  - Est. long-term average deliveries: 110,000 AF

- # State and Federal water supplies
- State Water Project (SWP)
    - Operated by CA DWR
    - 1961 First deliveries to Santa Clara County
    - Contract amount: 100,000 AF
    - Est. long-term average deliveries: 55,000 AF
  - Central Valley Project (CVP)
    - Operated by USBR
    - 1987 First deliveries to Santa Clara County
    - Contract amount: 152,500 AF
    - Est. long-term average deliveries: 110,000 AF

## Central Valley Project (CVP)


- Operated by USBR
- 1987 First deliveries to Santa Clara County
- Contract amount: 152,500 AF
- Est. long-term average deliveries: 110,000 AF

- ## Central Valley Project (CVP)
- Operated by USBR
  - 1987 First deliveries to Santa Clara County
  - Contract amount: 152,500 AF
  - Est. long-term average deliveries: 110,000 AF



# District map


Water Supply Distribution






# County's water supplies to treatment plants (2011 – 2021)

4






# IWU Groundwater Recharge (2016-2021)



# Valley Water Deliveries (1991-2021)





# Controlling Regulations

7

US Bureau of Reclamation

CA Department of Water  
Resources

State Water Board

National Marine Fisheries Service

U.S. Fish & Wildlife Service

CA Dept of Fish & Wildlife

State Water Contractors

San Luis & Delta Mendota Water  
Authority

Other Water Agencies

COA

Water  
Supply  
Contracts

ESA  
CESA

M&I  
Shortage  
Policy

CA Water  
Code

Warren Act

WQCP

Settlement  
Agreements

Water Rights

Court  
Decisions

Delta Plan

CVPIA

Operations  
Administrative  
Policies & Procedures  
Regulations  
Legislation  
Litigation

# 2022 Water Supply Conditions

- 2021 was drier than 2014 or 2015, driest year since 1977
- 2020/2021 combination is 2<sup>nd</sup> driest on record
- First three months of calendar year 2022 driest on record
- Low statewide storage conditions
- Valley Water's SWP and CVP allocations:
  - SWP: 5%
  - CVP M&I: PHS
  - CVP Ag: 0%





# 2022 Water Supply Conditions (Cont'd)

- FERC Order: Anderson Reservoir at Deadpool since late 2020
- Increased reliance on imported water for recharge and deliveries to water treatment plants



# San Luis Low Point


10



valleywater.org



# Key 2022 Regulatory Issues



- Drought Activity
  - Temporary Urgency Change Petition
  - State Board hearings and workshops
  - Curtailments & Emergency Regulations
- ITP/BiOps
  - Implementation
  - Re-initiation of consultation
  - Litigation
- WQCP Updates & Voluntary Agreements
- Species Status

# Long-Term Planning

- Delta Conveyance Project
- Groundwater Banking
- Surface Storage
  - Pacheco Reservoir
  - Sites Reservoir
  - Los Vaqueros Reservoir expansion
  - San Luis Reservoir expansion





# Drought Impacts



- Mitigate low allocations with Semitropic
  - exchange capacity and water quality issues
- Transfers
  - Scarcity
  - Cost
  - Conveyance capability issues
- Water Quality concerns
  - San Luis Reservoir and SBA
- State Board actions
  - Curtailments
  - Temporary Urgency Change Petitions

*Image credit: DWR. Governor Newsom at 2021 drought press conference.  
Location: lakebed in Mendocino County.*





# Pacheco Reservoir Expansion Project Update




# Existing North Fork Dam and Pacheco Reservoir

## Dam

- 100-foot-tall earthen embankment dam
- 0.4 miles upstream of North Fork Creek and South Fork Creek confluence
- Construction completed in 1939

## Reservoir


- Current capacity: 5,500 acre-feet
- Operated for groundwater recharge along Pacheco Creek by Pacheco Pass Water District





# Project Components


- **Dam** – approximately 300 feet high, one location under consideration
- **Reservoir** – up to 140 thousand acre-feet (TAF)
- **Spillway** – capable of passing the Maximum Probable Flood
- **Intake/Outlet Works** – large diameter pipe, smaller outlet pipe to Pacheco Creek
- **Pump Station & Conveyance Pipeline** – to transfer water to and from Pacheco Conduit
- **Roadways** – access to and from SR 152




# Existing & Proposed Dam Storage Capacity

4

Existing – 5,500 AF



Expanded – 140,000 AF



# Project Benefits


5

## ENVIRONMENTAL

Enhance habitat for federally threatened steelhead



Enhance water supply in below- normal years to wildlife refuges in the Delta



Increase water supply reliability and emergency water supply



Resolve the water quality problem in supply sourced from San Luis Reservoir




Reduce flooding along Pacheco Creek and to disadvantaged communities





# Project Partners


6





# Example of Partner Use

7



# Necessary Permits

8

## Federal

- USACE: CWA Section 404 Permit
- USFWS: ESA Section 7 Consultation
- NMFS: Incidental take permit (steelhead trout)

## State

- DSOD: New dam application
- CALTRANS: Encroachment Permit
- CDFW: LSAA & Section 2081
- SWRCB: General Construction NPDES Stormwater Permit
- SWRCB/SFRWQCB: CWA Section 401 Water Quality Certification
- SHPO: Section 106 of the NHPA

Local: Municipal approvals, encroachment permits, temporary rights of way



# Key Project Schedule Milestones

- Present Planning Study Report – [Fall 2021](#)
- Perform additional environmental investigations – [2021](#)
- Complete draft EIR for public review – [Feb 2022](#)
- Perform additional geotechnical investigations – [2022](#)
- Advertise for construction – [late 2024](#)



# Anderson Dam Seismic Retrofit Project Update

# Anderson Dam Seismic Retrofit Project

11

## Background

- Anderson Dam forms Anderson Reservoir, holding 90,000 acre feet of water when full and the largest of Valley Water's reservoirs.
- In 2012, following a seismic stability analysis, Valley Water began plans to retrofit the dam to meet current safety standards, creating the Anderson Dam Seismic Retrofit Project (ADSRP).
- On February 20, 2020, the Federal Energy Regulatory Commission (FERC) issued an order to Valley Water to undertake early implementation interim risk reduction measures associated with ADSRP immediately.




# Anderson Dam Existing Components

12




# Anderson Dam Seismic Retrofit Project Components





# FERC Directive: Risk Reduction Measures

14



1. Lower reservoir to new restriction (El. 565')



2. Take all necessary measures to safely prepare and drain the reservoir to El. 488'



3. Oct. 1 - Begin draining reservoir to dead pool (El. 488')



4. Develop plan to maintain dead pool elevation in event of significant inflow




5. Expedite design and construction of new Outlet Tunnel



6. Secure permits and complete design of larger Seismic Retrofit Project



## Anderson Dam Federal Energy Regulatory Commission Order Compliance Projects (FOCP)



## ADSRP

15

- Seismic retrofit of dam embankment
- Construction of new higher capacity outlet tunnel and outlet works
- Replacement of concrete spillway and raising wall height 9-feet to safely discharge large storm flows
- Increase dam crest height 7-feet




# FOCP Elements - Current Status

16

- Reservoir Drawdown to Deadpool and Maintain Level at Deadpool – Complete
- Anderson Dam Tunnel Project (ADTP) Construction – On-going
- Anderson Dam Tunnel Operation and Maintenance – Post ADTP Construction
- Bank and Rim Stability Improvements (Included in ADTP)
- Existing Intake Structure Modifications (Included in ADTP)
- Creek Channel and Bank Erosion Control Modifications (Included in ADTP)
- Imported Water Releases and Cross Valley Pipeline Extension – On-going
- Coyote Percolation Dam Replacement – In Design
- Coyote Creek Flood Management Measures – In Design
- Steelhead Fish Avoidance and Minimization Measures – In Design
- Implementation of Additional Project Specific Avoidance and Minimization Measures - In Planning/Design

# Anderson Reservoir at 3% Capacity - Map





# Anderson Dewatered

18



# Potential Impacts

19

- After storm events, the water level in the reservoir will rise temporarily
- Increased flows in Coyote Creek, downstream of the dam, after storm events
- Noise from construction equipment (large diesel engines) and backup alarms
- Work activities will mainly be Monday through Friday during the daytime, but some Saturdays may be required
- Smells caused by elevated levels of algae in the summer.  
Algal blooms can deplete oxygen levels in the water and produce hydrogen sulfide (rotten egg taste and odor)



# Necessary Permits

20

## Federal

- FERC: Amendment to Exemption for Licensing
- USACE: CWA Section 404 Permit
- USFWS: Incidental take permit (VHP – see below)
- NMFS: Incidental take permit (steelhead trout)


## State

- DSOD: New dam application
- CDFW: LSAA
- VHP: Incidental take authorization (covered species for state and federal ESA)
- SWRCB: General Construction NPDES Stormwater Permit
- SWRCB/SFRWQCB: CWA Section 401 Water Quality Certification
- SHPO: Section 106 of the NHPA

Local: Municipal approvals, encroachment permits, temporary rights of way

# Project Schedule

21





# QUESTIONS







# Permanente Creek Flood Protection Project

Water 101 Tour – May 11, 2022



# Project Objectives

- Provide 1% flood protection to Mountain View and Los Altos using a natural flood protection approach
- Address deteriorating concrete channels
- Provide opportunities for environmental enhancements and recreational benefits
- Minimize long-term maintenance cost



# Permanente Project Elements

**A** Floodwalls

**C** Channel widening

Flood detention areas:

**B** McKelvey Park

**D** Rancho San Antonio Park





# Project Cost

4

- Planning and Design: \$13M
- Construction: \$80M
- Construction Contract Amounts
  - McKelvey Detention Basin: \$31M
  - Rancho San Antonio Detention Basin: \$20M
  - Permanente Creek Channel Improvements: \$8M
- Funding Source
  - Watershed Stream Stewardship Fund
  - Safe Clean Water Fund

# Project Description

## Channel Improvements

5

- Floodwalls
- Channel Widening



valleywater.org



# Floodwall

6





# Channel Widening

7





# Project Description

## McKelvey Park

- Sunken fields
- 13 concrete retaining and soldier pile walls
- Weir & pump station
- Other park amenities



# Babe Ruth Field






# Little League Field

10





# Weir and Pump Station





# Pedestrian Bridge

12





# Babe Ruth Field Building

13





# Little League Field Building

14





# Community Building

15





# Mini Park (Shaefer Park)

16









# Project Description

## Rancho San Antonio

- Detention Basins
- Maintenance Bridge
- Restroom/Leach Field
- Parking Lot
- Planting



# Inlet Structure and South Basin

19





# North Basin and New Parking Lot

20





# North Basin

21





# Planting

22






# Completed Project Video

23

<https://www.youtube.com/watch?v=OpQJZb66hd8>



valleywater.org




# Upper Llagas Creek Project

May 11, 2022



# Upper Llagas Creek Flood Protection Project





# Flooding history

- Upper Llagas Creek has experienced flooding during major storm events in 1955, 1958, 1962, 1963, 1969, 1982, 1986, 1996, 1997, 1998, 2002, 2008, 2009, 2011, and 2017.



Oct.13, 2009



# Project objectives

Provide 100-year flood protection to Reaches 7 & 8

Provide 10-year level of flood protection in Reach 14 and no induced flooding in Reaches 4, 5 & 6

Other project specific objectives:

Design a stable channel  
Preserve and enhance habitat



# Major Project Components

Upper Llagas Creek Project

Creek widening  
and deepening

Bridge/culvert  
modifications

Utility  
relocations

105 acres of  
riparian  
planting

Construction of  
maintenance  
roads

Tunnel  
construction

Wetland  
creation and  
stream  
restoration


Property  
acquisitions

Long-term  
maintenance



# Phase 1 Construction 2019 - 2022

Reaches 4 (2.4 miles), 5 (2500 feet), 6 (1600 feet) 14 (1000 feet) 7a (1.5 miles), Lake Silveira Mitigation





# Phase 1 Construction 2019 - 2022



Reach 7a chute and pools, , Reach 4, revegetation Reach 7a





# Phase 1 Construction 2019 - 2022

Final excavations, planting, fencing, and collaboration with City of Morgan Hill






# Phase 2a Construction 2021 - 2023

Reach 8 includes construction of an underground bypass tunnel

Construction began June 2021

Flatiron Construction Corporation



 Phase 2A Work Area



# Phase 2a Construction 2021 - 2023


## Tunnel and culvert alignment





# Phase 2b Construction

Schedule to be determined





# Lake Silveira Compensatory Mitigation

Compensatory Mitigation for Project Impacts to state and federal waters

Pre-construction drone aerial  
(post-blackberry removal)




Upper Llagas Creek Flood Protection Project



# Lake Silveira

## Mitigation plan





# Lake Silveira Construction

Construction began May 1, 2020





# Lake Silveira 2022

Establishment and operation of the wetlands

